					ST DEPARTMENT DIVISION C		URAL RESC				AMENI	FC DED REPOR	RM 3	
		AF	PPLICATION FO	OR PERM	IIT TO DRILL					1. WELL NAME and N	UMBER NBU 921	-22K4CS		
2. TYPE O	F WORK	DRILL NEW WELL	REENTER	P&A WELL	. DEEPEN	WELL ()			3. FIELD OR WILDCA	T NATURAL	.BUTTES		
4. TYPE O	F WELL				hane Well: NO					5. UNIT or COMMUNI		AGREEM	ENT NAM	1E
6. NAME (OF OPERATOR		KERR-MCGEE OIL							7. OPERATOR PHONE				
8. ADDRE	SS OF OPERAT		P.O. Box 173779							9. OPERATOR E-MAII	L	anadarko	com	
	AL LEASE NUM		F.O. Box 173778	11. MI	NERAL OWNERS	SHIP				12. SURFACE OWNER		anauarko		
		JTU 010950-A	(C1)	FED	DERAL (III) INC	DIAN 🔵	STATE () FEE	0		DIAN 📵			EE 💮
		OWNER (if box 12								14. SURFACE OWNE		`		
15. ADDR	ESS OF SURFA	CE OWNER (if box	12 = 'fee')							16. SURFACE OWNE	R E-MAIL	(if box 12	! = 'fee')	
	N ALLOTTEE O	R TRIBE NAME			TEND TO COMM		RODUCTION	FROM		19. SLANT				
(11 BOX 12		te Indian Tribe		YES	(Submit C	Commingli	ng Application	on) NO		VERTICAL DII	RECTION	AL 📵 H	HORIZON	TAL 🔵
20. LOC/	ATION OF WELI	-		FOOTAGE	ES	QTF	R-QTR	SEC	TION	TOWNSHIP	RA	ANGE	МЕ	ERIDIAN
LOCATIO	N AT SURFACI		175	3 FSL 164	0 FWL	NE	ESW	2	2	9.0 S	2	1.0 E		S
Top of U	ppermost Prod	lucing Zone	1570	FSL 214	7 FWL	NE	ESW	2	2	9.0 S	2	1.0 E		S
At Total			1576	FSL 214	SL 2147 FWL NESW			2	2	9.0 S 2°		21.0 E S		S
21. COUN	ITY	UINTAH		22. DIS	22. DISTANCE TO NEAREST LEASE LINE (Feet) 1071 23. NUMBER OF ACRES IN DRILLING UNIT									
					25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 476 26. PROPOSED DEPTH MD: 11132 TVD: 11084									
27. ELEV	ATION - GROUN	ID LEVEL 4887		28. BC	OND NUMBER	WYB00	10291			29. SOURCE OF DRIL WATER RIGHTS APPR		MBER IF A	PPLICAB	LE
		4007			Hole, Casing			rmation						
String	Hole Size	Casing Size	Length	Weight	Grade & T	hread	Max Mu	ıd Wt.		Cement		Sacks	Yield	Weight
Surf	11	8.625	0 - 2830	28.0	J-55 L1	Г&С	0.	2		Type V		180	1.15	15.8
Prod	7.875	4.5	0 - 11132	11.6	HCP-110	LTRC	13	_	Pror	Class G mium Lite High Stre	nath	270 340	3.38	15.8
FIGU	7.075	4.5	0 - 11132	11.0	HCF-110	LIAC	13	.0	Fiel	50/50 Poz	iigiii	1590		14.3
					Δ	TTACH	MENTS			00/00 1 02		1000	1.01	11.0
	VEF	RIFY THE FOLLO	WING ARE AT	ACHED I	IN ACCORDAN	ICE WITI	H THE UTA	AH OIL A	ND GAS	CONSERVATION G	ENERA	L RULES		
⊮ w	ELL PLAT OR M	AP PREPARED BY	LICENSED SURVE	YOR OR E	NGINEER		сом	PLETE DR	ILLING PL	.AN				
AF	FIDAVIT OF STA	ATUS OF SURFACE	OWNER AGREEM	IENT (IF FE	EE SURFACE)		FORM	1 5. IF OPE	RATOR IS	OTHER THAN THE L	EASE OW	NER		
I DII	RECTIONAL SU	RVEY PLAN (IF DIR	ECTIONALLY OR	HORIZON	ITALLY DRILLED)	торо	GRAPHIC	AL MAP					
NAME La	ura Abrams			TITLE R	egulatory Analyst	: II			PHONE 7	20 929-6356				
SIGNATU	IRE			DATE 05	5/01/2012				EMAIL La	ura.Abrams@anadark	o.com			
	BER ASSIGNED 04752551			APPROV	/AL				Bol	Ryill				
									Permi	t Manager				

NBU 921-22K Pad Drilling Program

1 of 4

Kerr-McGee Oil & Gas Onshore, L.P.

NBU 921-22K4CS

Surface: 1753 FSL / 1640 FWL NESW BHL: 1576 FSL / 2147 FWL NESW

Section 22 T9S R21E

Unitah County, Utah Mineral Lease: UTU 010950-A

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. & 2.a <u>Estimated Tops of Important Geologic Markers</u>: Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1,581'	
Birds Nest	1,840'	Water
Mahogany	2,379'	Water
Wasatch	4,901'	Gas
Mesaverde	7,809'	Gas
Sego	10,019'	Gas
Castlegate	10,071'	Gas
MN5	10,484'	Gas
TVD =	11,084'	
TD =	11,132'	

2.c Kerr McGee Oil & Gas Onshore LP (Kerr McGee) will either drill to the the Blackhawk formation, which is part of the Mesaverde formation, or the Wasatch/Mesaverde formation. If Kerr McGee drills to the Blackhawk formation (part of the Mesaverde formation), please refer to MN5 as the bottom formation. The attached Blackhawk Drilling Program includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the deeper formation.

If Kerr McGee drills to the Wasatch/Mesaverde formation please refer to Sego as the bottom formation. The attached Wasatch/Mesaverde Drilling Program includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the depths the Wasatch/Mesaverde formations are found.

NBU 921-22K Pad Drilling Program 2 of 4

3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

4. <u>Proposed Casing & Cementing Program:</u>

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

5. Drilling Fluids Program:

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

6. Evaluation Program:

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

7. <u>Abnormal Conditions</u>:

7.a Blackhawk (Part of Mesaverde Formation) Target Formation

Maximum anticipated bottom hole pressure calculated at 7,315 psi (0.66 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 4,927 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

7.b Wasach/Mesaverde Target Formation

Maximum anticipated bottom hole pressure calculated at 10019' TVD, approximately equals 6,412 psi (0.64 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 4,194 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. <u>Variances:</u>

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program Onshore Order #2 – Air Drilling Variance

 $Kerr-McGee\ Oil\ \&\ Gas\ Onshore\ LP\ (KMG)\ respectfully\ requests\ a\ variance\ to\ several\ requirements\ associated\ with\ air\ drilling\ outlined\ in\ Onshore\ Order\ 2$

- · Blowout Prevention Equipment (BOPE) requirements;
- · Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

NBU 921-22K Pad Drilling Program
3 of 4

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

NBU 921-22K Pad Drilling Program
4 of 4

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

10. Other Information:

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program


NBU 921-22K Pad Drilling Program

1 of 2



KERR-McGEE OIL & GAS ONSHORE LP BLACKHAWK DRILLING PROGRAM

COMPANY NAME KER	R-McGEE OIL &	GAS ONSHORE	E LP		DATE	December	20, 2011		
WELL NAME NB	U 921-22K4C	S			TD	11,084'	TVD	11,132' MD	
FIELD Natural Butte	S	COUNTY	Uintah	STATE Uta	h	FINIS	HED ELEVATION_	4,887'	
SURFACE LOCATION	NESW	1753 FSL	1640 FWL	Sec 22	T 9S	R 21E			
	Latitude:	40.019132	Longitude	: -109.54	1467		NAD 83		
BTM HOLE LOCATION	NESW	1576 FSL	2147 FWL	Sec 22	T 9S	R 21E			
	Latitude:	40.018641	Longitude	: -109.53	9662		NAD 83		
OBJECTIVE ZONE(S)	BLACKHAWK		•			•			
ADDITIONAL INFO	Regulatory Age	ncies: BLM (Mir	erals). Ute Indi	ian Tribe (Su	ırface). U	DOGM Tri-Cou	inty Health Dept.		



NBU 921-22K Pad **Drilling Program** 2 of 2



KERR-McGEE OIL & GAS ONSHORE LP **BLACKHAWK DRILLING PROGRAM**

DESIGN FACTORS CASING PROGRAM CONDUCTOR

SURFACE PRODUCTION

SIZE	INT	ERVA	L	WT.	GR.	CPLG.	BURST	COLLAPSE	TE	ENSION
14"	C)-40'								
							3,390	1,880	348,000	N/A
8-5/8"	0	to	2,830	28.00	IJ-55	LTC	1.90	1.42	5.02	N/A
							10,690	8,650	279,000	367,174
4-1/2"	0	to	5,000	11.60	HCP-110	DQX	1.19	1.15		3.55
4-1/2"	5,000	to	11,132'	11.60	HCP-110	LTC	1.19	1.15	4.89	

Surface Casing:

0.73 psi/ft = frac gradient @ surface shoe (Burst Assumptions: TD = ppq)

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 9000 0.66 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1			+ 0.25 pps flocele				
TOP OUT CM	T (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE			NOTE: If well will circulate water t	o surface, op	tion 2 will be	utilized	
Option 2	LEAD	2,330'	65/35 Poz + 6% Gel + 10 pps gilsonite	210	35%	11.00	3.82
			+ 0.25 pps Flocele + 3% salt BWOW				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
			+ 0.25 pps flocele				
TOP C	OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	4,392'	Premium Lite II +0.25 pps	340	35%	12.00	3.38
			celloflake + 5 pps gilsonite + 10% gel				
			+ 0.5% extender				
	TAIL	6,740'	50/50 Poz/G + 10% salt + 2% gel	1,590	35%	14.30	1.31
			+ 0.1% R-3				

^{*}Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

PRODUCTION

Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well. □

1 centralizer on the first 3 joints and one every third joint thereafter.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Survev	's will	be	taken	at	1.000'	minimum	intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized

	Most rigs have i vi System for mut	a monitoring. If no t vi is available, visual monitoring will be utilized	u.	
DRILLING	ENGINEER:		DATE:	
		Nick Spence / Danny Showers / Chad Loesel	_	
DRILLING	SUPERINTENDENT:		DATE:	
		Kenny Gathings / Lovel Young	_	

LTC

DQX

^{*}Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

NBU 921-22K Pad **Drilling Program** 1 of 2



Mud logging program TBD

Cased hole logging program from TD - surf csg

Max anticipated


12.5 ppg

Mud required

Mesaverde @

TD@

Sego



7,809' TVD

10,019' TVD

10,019' TVD

10,067' MD

4-1/2" 11.6#

I-80/HCP-110

Ultra DQX/LTC csg

Water / Fresh

Water Mud

8.3-12.5 ppg

7-7/8"

NBU 921-22K Pad Drilling Program 2 of 2



KERR-McGEE OIL & GAS ONSHORE LP

WASATCH/MESAVERDE DRILLING PROGRAM

CASING PROGRAM DESIGN FACTORS LTC DQX INTERVAL GR. CPLG. **BURST** COLLAPSE **TENSION** SIZE WT. CONDUCTOR 14" 0-40' 3,390 1,880 348,000 N/A **SURFACE** 28.00 **IJ-55** 8-5/8" 2,830 LTC 1.90 1.42 5.02 N/A 6,350 267,035 7,780 **PRODUCTION** 4-1/2" 5,000 11.60 I-80 DQX 0.98 2.83 1.11 10,690 8,650 223,000

HCP-110

LTC

1.53

Surface Casing:

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

5.000

4-1/2"

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

10,067

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1		+ 0.25 pps flocele				
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
		+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water to	surface, opt	ion 2 will be	utilized	
Option 2 LEAD	2,330'	65/35 Poz + 6% Gel + 10 pps gilsonite	210	35%	11.00	3.82
		+ 0.25 pps Flocele + 3% salt BWOW				
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
		+ 0.25 pps flocele				
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION LEAD	4,397'	Premium Lite II +0.25 pps	340	35%	12.00	3.38
		celloflake + 5 pps gilsonite + 10% gel				
		+ 0.5% extender				
TAIL	5,670'	50/50 Poz/G + 10% salt + 2% gel	1,340	35%	14.30	1.31
		+ 0.1% R-3				

^{*}Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

PRODUCTION

Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well.

1 centralizer on the first 3 joints and one every third joint thereafter.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

	Surveys will be taken at 1,000' mini	mum intervals.		
	Most rigs have PVT System for mu	d monitoring. If no PVT is available, visual monitoring will be utilize	zed.	
DRILLING	ENGINEER:		DATE:	
		Nick Spence / Danny Showers / Chad Loesel		

DRILLING SUPERINTENDENT:


Kenny Gathings / Lovel Young

RECEIVED: April 24, 2012


DATE:

^{*}Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

EXHIBIT A NBU 921-22K4CS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



WELL NAME			SURFACE POS	SITION		BOTTOM HOLE NAD83 NAD27							
		AD83		NAD27									
NIDLI	40°01'08.89	LONGIT		DE LONG 018" 109°32		FOOTAGE:		TUDE 19.985"		GITUDE	LATITUDE	LONGITUDE 109°32'20.212"	FOOTAGES
NBU 921-22F4CS	40°01°08.89 40.019136°	1" 109°32'29 109.54143				1755' FSL 1650' FWL	40.022			2'22.690" 39636°	40.022253°	109°32'20.212" 109.538948°	2406' FNL 2148' FWL
NBU	40°01'08.870		0.282" 40°01'09.	003" 109°32		1753' FSL	40°01'	07.107"		2'22.784"	40°01'07.234"	109:330940 109°32'20.306"	
921-22K4CS	40.019132°	109.54146	57° 40.01916	8° 109.540)779°	1640' FWL	40.018			39662°	40.018676°	109.538974°	2147' FWL
NBU 921-22N1BS	40°01'08.86° 40.019128°	1" 109°32'29 109.54150				1751' FSL 1630' FWL	40°01′ 40.01 <i>7</i>	03.827" 730°	1	2'22.809" 39669°	40°01'03.954" 40.017765°	109°32'20.331" 109.538981°	1244' FSL 2147' FWL
NBU	40°01'08.84					1750' FSL		00.547"		2'22.847"	40°01'00.674"		912' FSL
921-22N1CS	40.019124°	109.54153	88° 40.01915	9° 109.540	0850°	1620' FWL	40.016	819°	109.53	39680°	40.016854°	109.538991°	2146' FWL
NBU	40°01'08.830			957" 109°32		1748' FSL		14.924"	1.000	2'26.772"			
921-22K2AS NBU	40.019120° 40°01'08.81	109.54157 5" 109°32'29		5° 109.540 942" 109°32		1611' FWL 1747' FSL	40.020	17.750"	_	40770° 2'26.262"	40.020848° 40°01'17.877"	109.540082° 109°32'23.785"	1832' FWL 2634' FNL
921-22F3DS	40.019115°	109.54160				1601' FWL	40.021			40628°	40.021632°	109 32 23.763 109.539940°	1870' FWL
NBU 194	40°01'08.983	.00 0==0		110" 109°32	25.916"	1764' FSL							•
	40.019162°	109.54122		1.00.0		1709' FWL							
				IVE COORD									
WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAS		L NAME	NOR	TH	EAST	WELL NAM	ME NORTH	EAST
NBU 921-22F4CS	1122.4'	504.11	NBU 921-22K4CS	-179.5	505.	5 NBU	22N1BS	-510	0.01	513.2	NBU 921-22N1C	-840.4	519.9'
WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAS		1		1			-	1
NBU NAME			NBU				4 :-		1				1
921-22K2AS	616.7'	225.5'	921-22F3DS	904.21	275.	$N_{2O^{\circ}OS,2S^{\prime\prime}E} / N_{O^{\circ}OS,2S^{\prime\prime}E} / N_{O^{\circ}OS}$	1		/				\
	AZ =	261 1177		107	10' 10' 1	TI) EXI	STING	WELL: NBU	J 194	
	S8	261 <u>.117</u> 1°07'04"V	78° — — N	921	921-22N CS 921-22K2AS AZ 921-23F3DS AZ	NBU 921-22F4CS AZ TO EX NBU 921-22K4CS AZ TO EX NBU 921-22K1BS AZ TO EX	So to Exit	`\ <u>\</u>	Z, Z	<u>, , , , , , , , , , , , , , , , , , , </u>	54861° 536.45' Hole)		
,09	30 ₁	CALE	109	921-221	921-22N CS 921-22K2AS AZ 921-22K2AS AZ	921-22F4CS AZ 10 921-22K4CS AZ 10 921-22N1BS AZ 1	53 (70 b) 111167° 60.0' 111278° 70.0'	`\ <u>\</u>	570/TO \$100 80000 0000000000000000000000000000	<u>, , , , , , , , , , , , , , , , , , , </u>	54861° 536.45° Hole)		
Kerr-Mc	30 ₁	CALE & Gas (Denver, Colo	Onshore, I	921-221	921-22N CS 921-22K2AS AZ 921-23F3DS AZ	921-22F4CS AZ 10 921-22K4CS AZ 10 921-22N1BS AZ 1	53 (60° 111278° 70.0'	A A A SOROM HOVE	1.05.00 00 00 00 00 00 00 00 00 00 00 00 00	<u>, , , , , , , , , , , , , , , , , , , </u>	36,	(4	35) 789-1365
Kerr-Mc 1099 1 WEI	Gee Oil 8th Street - D	CALE & Gas (Denver, Colo NBU 92	Onshore, I	921-221	921-22N CS 921-22K2AS AZ 921-23F3DS AZ	921-22F4CS AZ. to Exist. W.H.=81.13528° 80.0' 921-22K4CS AZ. to Exist. W.H.=81.13889° 90.0' 921-22N1BS AZ. to Exist. W.H.=81.13333° 100.0'	53 (70 b) 111278° 70.0'	TI	10.500 80.10) 10.500 80.12)	SERLI	Seo.	(4. SURVEYING	
Kerr-Mc 1099 1 WEI	Gee Oil 18th Street - D LL PAD -	CALE & Gas (Denver, Colo NBU 92 ERFEREN	Onshore, Irado 80202 21-22K	921-221-3	921-22N CS 921-22K2AS AZ 921-23F3DS AZ	921-22F4CS AZ. to Exist. W.H.=81.13528° 80.0' 921-22K4CS AZ. to Exist. W.H.=81.13889° 90.0' 921-22N1BS AZ. to Exist. W.H.=81.13333° 100.0'	53 (70 b) 111278° 70.0'	TI	Solo Bolton	BERLI NEERIN	INE		G, INC.
Kerr-Mc 1099 1 WEI WELL WELLS - N	Gee Oil 18th Street - D LL PAD - PAD INT NBU 921-22	& Gas (Denver, Colo NBU 92 ERFEREN K2AS, NBU	Onshore, Irado 80202 21-22K NCE PLAT J 921-22K4CS	921-221-3	921-22N C3 921-22K2AS Az, to Exist. W.H.=81.12944° 110.0 921-22F3DS Az. to Exist. W.H.=81.12944°	921-22F4CS AZ. to Exist. W.H.=81.13528° 80.0' 921-22K4CS AZ. to Exist. W.H.=81.13889° 90.0' 921-22N1BS AZ. to Exist. W.H.=81.13333° 100.0'	53 (70 bc / 11167° 60.0' 111278° 70.0'	TI E DATI	IME 209 E SURV	BERLI NEERIN NORTH 3	INE IG & LAND 300 WEST - VER	SURVEYINC RNAL, UTAH 840	G, INC.
Kerr-Mc 1099 1 WEI WELL WELLS - N NBU	5 S S S S S S S S S S S S S S S S S S S	& Gas (Denver, Colo NBU 92 ERFEREN K2AS, NBU 92 S, NBU 92	Onshore, Irado 80202 21-22K NCE PLAT J 921-22K4CS	921-221 S	921-22N C3 921-22K2AS Az. to Exist. W.H.=81.12944° 110.0 921-22K2AS Az. to Exist. W.H.=81.12944° 10.0 ON NO. 22155 No. 2215	921-22F4CS Az. to Exist. W.H.=81.13528° 80.0' 921-22K4CS Az. to Exist. W.H.=81.13889° 90.0' 921-22N1BS Az. to Exist. W.H.=81.13889° 90.0' 921-22N1BS Az. to Exist. W.H.=81.13333° 100.0' G. Az. to Exist. W.H.=81.13333° 100.0' Junth Manner of the Control of the	S3 (70 b) (11167° 60.0') (2 te	TI DATI 8-4-1	IME 209 E SURV	BERLI NEERIN NORTH 3	INE IG & LAND SOO WEST - VER SURVEYED B	SURVEYINC RNAL, UTAH 840 BY: M.B.	G, INC. 078
Kerr-Mc 1099 1 WEIL WELLS - N NBU NBU	Gee Oil 18th Street - D LL PAD - PAD INT NBU 921-22 921-22N1B 921-22F3DS	CALE & Gas (Denver, Colo NBU 92 ERFEREN K2AS, NBU 92 S & NBU 92	Onshore, Indoor 10 10 10 10 10 10 10 10 10 10 10 10 10	921-221 S	921-22N CS 921-22K2AS Az. to Exist. W.H.=81.12944° 110.0 921-22K2AS Az. to Exist. W.H.=81.12944° 110.0 ONS Sherida 2155 No.	921-22F4CS Az. to Exist. W.H.=81.13528° 80.0' 921-22K4CS Az. to Exist. W.H.=81.13528° 90.0' 921-22N1BS Az. to Exist. W.H.=81.13889° 90.0' 921-22N1BS Az. to Exist. W.H.=81.13333° 100.0' Juntal W.H.=81.13333° 100.0'	53 (70 8) (11167° 60.0) C et 1	TI DATI 8-4-1	IME 209 E SURVILLE E DRAW	BERLI NEERIN NORTH 3	INE IG & LAND 300 WEST - VER SURVEYED B DRAWN BY:	SURVEYINC RNAL, UTAH 840 BY: M.B.	G, INC.
WELL WELLS - NBU NBU SLOCA	5 S S S S S S S S S S S S S S S S S S S	& Gas (Denver, Colo NBU 9: ERFEREN K2AS, NBU 9: S, NBU 9: S & NBU 9: CTION 22,	Onshore, In the state of the st	921-221 S	921-22N CS 921-22K2AS Az. to Exist. W.H.=81.12944° 110.0 921-22K2AS Az. to Exist. W.H.=81.12944° 110.0 ONS No. 2155 N	921-22F4CS Az. to Exist. W.H.=81.13528° 80.0' 921-22K4CS Az. to Exist. W.H.=81.13889° 90.0' 921-22N1BS Az. to Exist. W.H.=81.13889° 90.0' 921-22N1BS Az. to Exist. W.H.=81.13333° 100.0' G. Az. to Exist. W.H.=81.13333° 100.0' Junth Manner of the Control of the	53 (70 8) (10 11278° 70.0' C et 10 0	TI BATI BATI BATI B-27:	ENGII 209 E SURV	BERLI NEERIN NORTH 3	INE IG & LAND SOO WEST - VER SURVEYED B	SURVEYINC RNAL, UTAH 840 BY: M.B. : J.G.C. vised:	G, INC.

Sheridan, WY 82801

Phone 307-674-0609 Fax 307-674-0182 ENGINEERING & LAND SURVEYING, INC.

209 NORTH 300 WEST - VERNAL, UTAH 84078

K:\ANADARKO\2011\2011_44_NBU_FOCUS_921-22\DWG\NBU 921-22K\NBU 921-2

LOCATED IN SECTION 22, T9S, R21E,

S.L.B.&M., UINTAH COUNTY, UTAH

REVISED:

GRB 10/21/11

8

8 OF 18

NADARKO\2011\2011_44_NBU_FOCUS_921-22\DWG\NBU 921-22K\

NBU 921-22N1BS, NBU 921-22N1CS,

NBU 921-22F3DS & NBU 921-22F4CS

LOCATED IN SECTION 22, T9S, R21E,

S.L.B.&M., UINTAH COUNTY, UTAH

CONSULTING, LLC

2155 North Main Street

Sheridan, WY 82801

Phone 307-674-0609 Fax 307-674-0182 **TIMBERLINE**

ENGINEERING & LAND SURVEYING, INC.

209 NORTH 300 WEST - VERNAL, UTAH 84078

12/1/11 SHEET NO:


 $8B_{8B \, \underline{OF} \, 18}$

1"=60' DATE:

(435) 789-1365

SCALE:

REVISED:






PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE

CAMERA ANGLE: NORTHERLY



PHOTO VIEW: FROM EXISTING ACCESS ROAD

CAMERA ANGLE: EASTERLY

Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-22K

LOCATION PHOTOS NBU 921-22K2AS, NBU 921-22K4CS, NBU 921-22N1BS, NBU 921-22N1CS, NBU 921-22F3DS & NBU 921-22F4CS LOCATED IN SECTION 22, T9S, R21E, S.L.B.&M., UINTAH COUNTY, UTAH.



CONSULTING, LLC 2155 North Main Street Sheridan WY 82801 Phone 307-674-0609 Fax 307-674-0182


TIMBERLINE


(435) 789-1365


11 OF 18


ENGINEERING & LAND SURVEYING, INC. 209 NORTH 300 WEST - VERNAL, UTAH 84078


DATE PHOTOS TAKEN: 7-19-11	PHOTOS TAKEN BY: M.B.	SHEET NO:
DATE DRAWN: 8-29-11	DRAWN BY: T.J.R.	11
Date Last Revised: 10-21-1	1 J.G.C.	11 OF 18














Kerr-McGee Oil & Gas Onshore, LP WELL PAD - NBU 921-22K WELLS - NBU 921-22K2AS, NBU 921-22K4CS, NBU 921-22N1BS, NBU 921-22N1CS, NBU 921-22F3DS & NBU 921-22F4CS Section 22, T9S, R21E, S.L.B.&M.

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah, proceed in an easterly then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 17.7 miles to a Class D County Road to the southwest. Exit right and proceed in a southwesterly direction along the Class D County Road approximately 1.8 miles to a second Class D County Road to the north. Exit right and proceed in a northerly direction along the second Class D County Road approximately 0.7 miles to a service road to the east. Exit right and proceed in an easterly direction along the service road approximately 0.1 miles to the proposed well location.

Total distance from Vernal, Utah to the proposed well location is approximately 43.8 miles in a southerly direction.

SHEET 18 OF 18

API Well Number: 43047 Bio Feot Coutan - UTM (feet), NAD27, Zone 12N

Scientific Drilling

Vertical Section at 109.52° (1500 ft/in)


Site: NBU 921-22K PAD Well: NBU 921-22K4CS


Wellbore: OH

Design: PLAN #1 PRELIMINARY











US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N NBU 921-22K PAD NBU 921-22K4CS

OH

Plan: PLAN #1 PRELIMINARY

Standard Planning Report

21 November, 2011





SDIPlanning Report



Database: EDM5000-RobertS-Local

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-22K PAD

 Well:
 NBU 921-22K4CS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 921-22K4CS

GL 4887 & KB 4 @ 4891.00ft (ASSUMED) GL 4887 & KB 4 @ 4891.00ft (ASSUMED)

True

Minimum Curvature

Project UTAH - UTM (feet), NAD27, Zone 12N

Map System: Universal Transverse Mercator (US Survey Feet)

 Geo Datum:
 NAD 1927 (NADCON CONUS)

 Map Zone:
 Zone 12N (114 W to 108 W)

Mean Sea Level

Site NBU 921-22K PAD, SECTION 22 T9S R21E

Northing: 14,536,368.06 usft Site Position: Latitude: 40° 1' 8.987 N From: Lat/Long Easting: 2,048,967.31 usft Longitude: 109° 32' 26.930 W **Position Uncertainty:** 0.00 ft Slot Radius: **Grid Convergence:** 0.94 13.200 in

System Datum:

Well NBU 921-22K4CS, 1753 FSL 1640 FWL

 Well Position
 +N/-S
 1.82 ft
 Northing:
 14,536,370.04 usft
 Latitude:
 40° 1′ 9.005 N

 +E/-W
 9.80 ft
 Easting:
 2,048,977.08 usft
 Longitude:
 109° 32′ 26.804 W

Position Uncertainty 0.00 ft Wellhead Elevation: Ground Level: 4,887.00 ft

Wellbore ОН Field Strength Magnetics **Model Name** Sample Date Declination Dip Angle (nT) (°) (°) IGRF2010 2011/11/18 11.04 65.86 52.292

PLAN #1 PRELIMINARY Design Audit Notes: Version: Phase: PLAN Tie On Depth: 0.00 **Vertical Section:** Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 109.52

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
850.00	11.00	109.52	846.63	-17.59	49.61	2.00	2.00	0.00	109.52	
3,069.48	11.00	109.52	3,025.33	-159.09	448.77	0.00	0.00	0.00	0.00	
3,698.06	0.00	0.00	3,650.05	-179.18	505.46	1.75	-1.75	0.00	180.00	
11,132.01	0.00	0.00	11,084.00	-179.18	505.46	0.00	0.00	0.00	0.00 I	PBHL_NBU 921-22K



SDIPlanning Report



Database: EDM5000-RobertS-Local

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-22K PAD

 Well:
 NBU 921-22K4CS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 921-22K4CS

GL 4887 & KB 4 @ 4891.00ft (ASSUMED) GL 4887 & KB 4 @ 4891.00ft (ASSUMED)

True

ned Survey									
Measured Depth (ft)	Inclination A	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00 100.00 200.00 300.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 100.00 200.00 300.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00
Start Build 2		0.00	000.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	2.00	109.52	399.98	-0.58	1.64	1.75	2.00	2.00	0.00
500.00 600.00 700.00 800.00	4.00 6.00 8.00 10.00	109.52 109.52 109.52 109.52	499.84 599.45 698.70 797.47	-2.33 -5.24 -9.32 -14.54	6.58 14.79 26.28 41.02	6.98 15.69 27.88 43.52	2.00 2.00 2.00 2.00	2.00 2.00 2.00 2.00	0.00 0.00 0.00 0.00
850.00	11.00	109.52	846.63	-17.59	49.61	52.63	2.00	2.00	0.00
Start 2219.48	hold at 850.00 MD								
900.00 1,000.00 1,100.00 1,200.00 1,300.00	11.00 11.00 11.00 11.00 11.00	109.52 109.52 109.52 109.52 109.52	895.71 993.87 1,092.03 1,190.20 1,288.36	-20.77 -27.15 -33.52 -39.90 -46.28	58.60 76.59 94.57 112.55 130.54	62.17 81.26 100.34 119.42 138.50	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00
1,400.00 1,500.00 1,598.12	11.00 11.00 11.00	109.52 109.52 109.52	1,386.52 1,484.69 1,581.00	-52.65 -59.03 -65.28	148.52 166.51 184.15	157.58 176.66 195.38	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
GREEN RIVE	R								
1,600.00 1,700.00	11.00 11.00	109.52 109.52	1,582.85 1,681.01	-65.40 -71.78	184.49 202.48	195.74 214.82	0.00 0.00	0.00 0.00	0.00 0.00
1,800.00 1,861.97	11.00 11.00	109.52 109.52	1,779.17 1,840.00	-78.15 -82.10	220.46 231.60	233.90 245.73	0.00 0.00	0.00 0.00	0.00 0.00
BIRDSNEST									
1,900.00 2,000.00 2,100.00	11.00 11.00 11.00	109.52 109.52 109.52	1,877.34 1,975.50 2,073.66	-84.53 -90.90 -97.28	238.44 256.43 274.41	252.98 272.06 291.15	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
2,200.00 2,300.00 2,400.00 2,411.05	11.00 11.00 11.00 11.00	109.52 109.52 109.52 109.52	2,171.82 2,269.99 2,368.15 2,379.00	-103.65 -110.03 -116.40 -117.11	292.40 310.38 328.37 330.35	310.23 329.31 348.39 350.50	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00
MAHOGANY									
2,500.00 2,600.00 2,700.00 2,800.00	11.00 11.00 11.00 11.00	109.52 109.52 109.52 109.52	2,466.31 2,564.48 2,662.64 2,760.80	-122.78 -129.15 -135.53 -141.91	346.35 364.33 382.32 400.30	367.47 386.55 405.63 424.71	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00
2,869.48 8 5/8"	11.00	109.52	2,829.00	-146.33	412.80	437.97	0.00	0.00	0.00
2,900.00	11.00	109.52	2,858.96	-148.28	418.29	443.79	0.00	0.00	0.00
3,000.00 3,069.48	11.00 11.00	109.52 109.52	2,957.13 3,025.33	-154.66 -159.09	436.27 448.77	462.87 476.13	0.00 0.00	0.00 0.00	0.00 0.00
Start Drop -1	.75								
3,100.00 3,200.00 3,300.00	10.47 8.72 6.97	109.52 109.52 109.52	3,055.32 3,153.91 3,252.98	-160.98 -166.55 -171.11	454.12 469.83 482.69	481.81 498.48 512.12	1.75 1.75 1.75	-1.75 -1.75 -1.75	0.00 0.00 0.00
3,400.00 3,500.00 3,600.00 3,698.06	5.22 3.47 1.72 0.00	109.52 109.52 109.52 0.00	3,352.41 3,452.12 3,552.01 3,650.05	-174.65 -177.18 -178.69 -179.18	492.69 499.82 504.08 505.46	522.73 530.30 534.82 536.29	1.75 1.75 1.75 1.75	-1.75 -1.75 -1.75 -1.75	0.00 0.00 0.00 0.00
	5 hold at 3698.06 M 0.00		3,652.00	-179.18	505.46	536.29	0.00	0.00	0.00



SDI Planning Report



Database: EDM5000-RobertS-Local

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-22K PAD

 Well:
 NBU 921-22K4CS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 921-22K4CS

GL 4887 & KB 4 @ 4891.00ft (ASSUMED) GL 4887 & KB 4 @ 4891.00ft (ASSUMED)

True

Design:	FLAN#1FRE								
Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,800.00	0.00	0.00	3,752.00	-179.18	505.46	536.29	0.00	0.00	0.00
3,900.00	0.00	0.00	3,852.00	-179.18	505.46	536.29	0.00	0.00	0.00
4,000.00	0.00	0.00	3,952.00	-179.18	505.46	536.29	0.00	0.00	0.00
4,100.00	0.00	0.00	4,052.00	-179.18	505.46	536.29	0.00	0.00	0.00
4,200.00	0.00	0.00	4,152.00	-179.18	505.46	536.29	0.00	0.00	0.00
4,300.00	0.00	0.00	4,252.00	-179.18	505.46	536.29	0.00	0.00	0.00
4,400.00	0.00	0.00	4,352.00	-179.18	505.46	536.29	0.00	0.00	0.00
4,500.00	0.00	0.00	4,452.00	-179.18	505.46	536.29	0.00	0.00	0.00
4,600.00	0.00	0.00	4,552.00	-179.18	505.46	536.29	0.00	0.00	0.00
4,700.00	0.00	0.00	4,652.00	-179.18	505.46	536.29	0.00	0.00	0.00
4,800.00 4,900.00 4,949.01 WASATCH	0.00 0.00 0.00	0.00 0.00 0.00	4,752.00 4,852.00 4,901.00	-179.18 -179.18 -179.18	505.46 505.46 505.46	536.29 536.29 536.29	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
5,000.00	0.00	0.00	4,952.00	-179.18	505.46	536.29	0.00	0.00	0.00
5,100.00	0.00	0.00	5,052.00	-179.18	505.46	536.29	0.00	0.00	0.00
5,200.00	0.00	0.00	5,152.00	-179.18	505.46	536.29	0.00	0.00	0.00
5,300.00	0.00	0.00	5,252.00	-179.18	505.46	536.29	0.00	0.00	0.00
5,400.00	0.00	0.00	5,352.00	-179.18	505.46	536.29	0.00	0.00	0.00
5,500.00	0.00	0.00	5,452.00	-179.18	505.46	536.29	0.00	0.00	0.00
5,600.00	0.00	0.00	5,552.00	-179.18	505.46	536.29	0.00	0.00	0.00
5,700.00	0.00	0.00	5,652.00	-179.18	505.46	536.29	0.00	0.00	0.00
5,800.00	0.00	0.00	5,752.00	-179.18	505.46	536.29	0.00	0.00	0.00
5,900.00	0.00	0.00	5,852.00	-179.18	505.46	536.29	0.00	0.00	0.00
6,000.00	0.00	0.00	5,952.00	-179.18	505.46	536.29	0.00	0.00	0.00
6,100.00	0.00	0.00	6,052.00	-179.18	505.46	536.29	0.00	0.00	0.00
6,200.00	0.00	0.00	6,152.00	-179.18	505.46	536.29	0.00	0.00	0.00
6,300.00	0.00	0.00	6,252.00	-179.18	505.46	536.29	0.00	0.00	0.00
6,400.00 6,500.00 6,600.00 6,700.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	6,352.00 6,452.00 6,552.00 6,652.00	-179.18 -179.18 -179.18 -179.18	505.46 505.46 505.46 505.46	536.29 536.29 536.29 536.29	0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00
6,800.00	0.00	0.00	6,752.00	-179.18	505.46	536.29	0.00	0.00	0.00
6,900.00	0.00	0.00	6,852.00	-179.18	505.46	536.29	0.00	0.00	0.00
7,000.00	0.00	0.00	6,952.00	-179.18	505.46	536.29	0.00	0.00	0.00
7,100.00	0.00	0.00	7,052.00	-179.18	505.46	536.29	0.00	0.00	0.00
7,200.00	0.00	0.00	7,152.00	-179.18	505.46	536.29	0.00	0.00	0.00
7,300.00	0.00	0.00	7,252.00	-179.18	505.46	536.29	0.00	0.00	0.00
7,400.00	0.00	0.00	7,352.00	-179.18	505.46	536.29	0.00	0.00	0.00
7,500.00	0.00	0.00	7,452.00	-179.18	505.46	536.29	0.00	0.00	0.00
7,600.00	0.00	0.00	7,552.00	-179.18	505.46	536.29	0.00	0.00	0.00
7,700.00 7,800.00 7,857.01 MESAVERDE	0.00 0.00 0.00	0.00 0.00 0.00	7,652.00 7,752.00 7,809.00	-179.18 -179.18 -179.18	505.46 505.46 505.46	536.29 536.29 536.29	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
7,900.00	0.00	0.00	7,852.00	-179.18	505.46	536.29	0.00	0.00	0.00
8,000.00	0.00	0.00	7,952.00	-179.18	505.46	536.29	0.00	0.00	0.00
8,100.00	0.00	0.00	8,052.00	-179.18	505.46	536.29	0.00	0.00	0.00
8,200.00	0.00	0.00	8,152.00	-179.18	505.46	536.29	0.00	0.00	0.00
8,300.00	0.00	0.00	8,252.00	-179.18	505.46	536.29	0.00	0.00	0.00
8,400.00	0.00	0.00	8,352.00	-179.18	505.46	536.29	0.00	0.00	0.00
8,500.00	0.00	0.00	8,452.00	-179.18	505.46	536.29	0.00	0.00	0.00
8,600.00	0.00	0.00	8,552.00	-179.18	505.46	536.29	0.00	0.00	0.00
8,700.00	0.00	0.00	8,652.00	-179.18	505.46	536.29	0.00	0.00	0.00



SDI Planning Report



Database: Company:

Project:

EDM5000-RobertS-Local

US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-22K PAD

 Well:
 NBU 921-22K4CS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 921-22K4CS

GL 4887 & KB 4 @ 4891.00ft (ASSUMED) GL 4887 & KB 4 @ 4891.00ft (ASSUMED)

True

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
8,800.00	0.00	0.00	8,752.00	-179.18	505.46	536.29	0.00	0.00	0.00
8,900.00	0.00	0.00	8,852.00	-179.18	505.46	536.29	0.00	0.00	0.00
9,000.00	0.00	0.00	8,952.00	-179.18	505.46	536.29	0.00	0.00	0.00
9,100.00	0.00	0.00	9,052.00	-179.18	505.46	536.29	0.00	0.00	0.00
9,200.00	0.00	0.00	9,152.00	-179.18	505.46	536.29	0.00	0.00	0.00
9,300.00	0.00	0.00	9,252.00	-179.18	505.46	536.29	0.00	0.00	0.00
9,400.00	0.00	0.00	9,352.00	-179.18	505.46	536.29	0.00	0.00	0.00
9,500.00	0.00	0.00	9,452.00	-179.18	505.46	536.29	0.00	0.00	0.00
9,600.00	0.00	0.00	9,552.00	-179.18	505.46	536.29	0.00	0.00	0.00
9,700.00	0.00	0.00	9,652.00	-179.18	505.46	536.29	0.00	0.00	0.00
9,800.00	0.00	0.00	9,752.00	-179.18	505.46	536.29	0.00	0.00	0.00
9,900.00	0.00	0.00	9,852.00	-179.18	505.46	536.29	0.00	0.00	0.00
10,000.00	0.00	0.00	9,952.00	-179.18	505.46	536.29	0.00	0.00	0.00
10,067.01	0.00	0.00	10,019.00	-179.18	505.46	536.29	0.00	0.00	0.00
SEGO									
10,100.00	0.00	0.00	10,052.00	-179.18	505.46	536.29	0.00	0.00	0.00
10,119.01	0.00	0.00	10,071.00	-179.18	505.46	536.29	0.00	0.00	0.00
10,200.00	0.00	0.00	10,152.00	-179.18	505.46	536.29	0.00	0.00	0.00
10,200.00	0.00	0.00	10,152.00	-179.18 -179.18	505.46 505.46	536.29 536.29	0.00	0.00	0.00
,			•						
10,400.00	0.00	0.00	10,352.00	-179.18	505.46	536.29	0.00	0.00	0.00
10,500.00	0.00	0.00	10,452.00	-179.18	505.46	536.29	0.00	0.00	0.00
10,532.01	0.00	0.00	10,484.00	-179.18	505.46	536.29	0.00	0.00	0.00
10,600.00	K - BLACKHAW 0.00	K_NBU 921-221 0.00	10,552.00	-179.18	505.46	536.29	0.00	0.00	0.00
10,700.00	0.00	0.00	10,652.00	-179.18	505.46	536.29	0.00	0.00	0.00
,			•						
10,800.00 10,900.00	0.00 0.00	0.00 0.00	10,752.00 10,852.00	-179.18 -179.18	505.46 505.46	536.29 536.29	0.00 0.00	0.00 0.00	0.00 0.00
11,000.00	0.00	0.00	10,852.00	-179.18 -179.18	505.46 505.46	536.29 536.29	0.00	0.00	0.00
11,100.00	0.00	0.00	11,052.00	-179.16 -179.18	505.46 505.46	536.29	0.00	0.00	0.00
11,132.01	0.00	0.00	11,084.00	-179.18	505.46	536.29	0.00	0.00	0.00

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
BLACKHAWK_NBU 921 - plan hits target cent - Circle (radius 25.00)		0.00	10,484.00	-179.18	505.46	14,536,199.16	2,049,485.41	40° 1' 7.234 N	109° 32' 20.306 W
PBHL_NBU 921-22K4C: - plan hits target cent - Circle (radius 100.00		0.00	11,084.00	-179.18	505.46	14,536,199.16	2,049,485.41	40° 1' 7.234 N	109° 32' 20.306 W

Casing Points							
	Measured Depth	Vertical Depth			Casing Diameter	Hole Diameter	
	(ft)	(ft)		Name	(in)	(in)	
	2,869.48	2,829.00	8 5/8"		8.625	11.000	



SDI **Planning Report**



Database: Company: EDM5000-RobertS-Local

US ROCKIES REGION PLANNING UTAH - UTM (feet), NAD27, Zone 12N

Project: NBU 921-22K PAD Site: Well: NBU 921-22K4CS

Wellbore: ОН

Design:

PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well NBU 921-22K4CS

GL 4887 & KB 4 @ 4891.00ft (ASSUMED) GL 4887 & KB 4 @ 4891.00ft (ASSUMED)

ormations						
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
	1,598.12	1,581.00	GREEN RIVER			
	1,861.97	1,840.00	BIRDSNEST			
	2,411.05	2,379.00	MAHOGANY			
	4,949.01	4,901.00	WASATCH			
	7,857.01	7,809.00	MESAVERDE			
	10,067.01	10,019.00	SEGO			
	10,119.01	10,071.00	CASTLEGATE			
	10,532.01	10,484.00	BLACKHAWK			

Plan Annotatio	ons				
	Measured	Vertical	Local Coor	dinates	
	Depth	Depth	+N/-S	+E/-W	
	(ft)	(ft)	(ft)	(ft)	Comment
	300.00	300.00	0.00	0.00	Start Build 2.00
	850.00	846.63	-17.59	49.61	Start 2219.48 hold at 850.00 MD
	3,069.48	3,025.33	-159.09	448.77	Start Drop -1.75
	3,698.06	3,650.05	-179.18	505.46	Start 7433.95 hold at 3698.06 MD
	11,132.01	11,084.00	-179.18	505.46	TD at 11132.00

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 1 of 12

Kerr-McGee Oil & Gas Onshore. L.P.

NBU 921-22K Pad

<u>API #</u>		NBU 921-22F3DS		
	Surface:	1747 FSL / 1601 FWL	NESW	Lot
	BHL:	2634 FNL / 1870 FWL	SENW	Lot
<u>API #</u>		NBU 921-22F4CS		
	Surface:	1755 FSL / 1650 FWL	NESW	Lot
	BHL:	2406 FNL / 2148 FWL	SENW	Lot
<u>API #</u>		NBU 921-22K2AS		
	Surface:	1748 FSL / 1611 FWL	NESW	Lot
	BHL:	2366 FSL / 1832 FWL	NESW	Lot
<u>API #</u>		NBU 921-22K4CS		
	Surface:	1753 FSL / 1640 FWL	NESW	Lot
	BHL:	1576 FSL / 2147 FWL	NESW	Lot
<u>API #</u>		NBU 921-22N1BS		
	Surface:	1751 FSL / 1630 FWL	NESW	Lot
	BHL:	1244 FSL / 2147 FWL	SESW	Lot
<u>API #</u>		NBU 921-22N1CS		
	Surface:	1750 FSL / 1620 FWL	NESW	Lot
	BHL:	912 FSL / 2146 FWL	SESW	Lot

This Surface Use Plan of Operations (SUPO) or 13-point plan provides site-specific information for the above-referenced wells.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

An on-site meeting was held on October 3-4, 2011. Present were:

- ъ
- · Bucky Secakuku (10/4/2011 only) BIA;
- · LeAllen Blackhair, Rainey Longhair Ute Indian Tribe;
- · Kelly Jo Jackson Montgomery Archeological Consultants Inc.;
- Scott Carson Smiling Lake Consulting;
- · John Slaugh, Mitch Batty Timberline Engineering & Land Surveying, Inc.;
- Laura Abrams, Charles Chase, Raleen White, Doyle Holmes, Lovel Young, Sheila Wopsock Kerr-McGee

A. Existing Roads:

Existing roads consist of county and improved/unimproved access roads (two-tracks). In accordance with Onshore Order #1, Kerr-McGee will, in accordance with BMPs, improve or maintain existing roads in a condition that is the same as or better than before operations began. New or reconstructed proposed access roads are discussed in Section B.

The existing roads will be maintained in a safe and usable condition. Maintenance for existing roads will continue until final abandonment and reclamation of well pads and/or other facilities, as applicable. Road maintenance will include, but is not limited to, blading, ditching, and/or culvert installation and cleanout. To ensure safe operating conditions, gravel surfacing will be performed where excessive rutting or erosion may occur. Dust control will be performed as necessary to ensure safe operating conditions.

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 2 of 12

Roads, gathering lines and electrical distribution lines will occupy common disturbance corridors where possible. Where available, roadways will be used as the staging area and working space for installation of gathering lines. All disturbances located in the same corridor will overlap each other to the maximum extent possible, while maintaining safe and sound construction and installation practices. Unless otherwise approved or requested in site specific documents, in no case will the maximum disturbance widths of the access road and utility corridors exceed the widths specified in Part D of this document.

Please refer to Topo B, for existing roads.

B. New or Reconstructed Access Roads:

All new or reconstructed roads will be located, designed, and maintained to meet the standards of the BIA.

Each new well pad or pad expansion may require construction of a new access road and/or de-commissioning of an older road. Plans, routes, and distances for new roads and road improvements are provided in design packages, exhibits and maps for a project. Project-specific maps are submitted to depict the locations of existing, proposed, and/or decommissioned and include the locations for supporting structures, including, but not limited to, culverts, bridges, low water crossings, range infrastructure, and haul routes, as per OSO 1. Designs for cuts and fills, including spoils source and storage areas, are provided with the road designs, as necessary.

Where safety objectives can be met. As applicable, Kerr-McGee may use unimproved and/or two-track roads for lease operations, to lessen total disturbance.

Road designs will be based on the road safety requirements, traffic characteristics, environmental conditions, and the vehicles the road is intended to carry. Generally, newly constructed unpaved lease roads will be crowned and ditched with the running surfaces of the roads approximately 12-18 feet wide and a total road corridor width not to exceed 45 feet, except where noted in the road design for a specific project. Maximum grade will generally not exceed 8%. Borrow ditches will be back sloped 3:1 or less. Construction BMPs will be employed to control onsite and offsite erosion.

Where topography would direct storm water runoff to an access road or well pad, drainage ditches or other common drainage control facilities, such as V- or wing-ditches, will be constructed to divert surface water runoff. Drainage features, including culverts, will be constructed or installed prior to commencing other operations, including drilling or facilities placement. Riprap will be placed at the inlet and outlet at the culvert(s), as necessary.

Prior to construction, new access road(s) will be staked according to the requirements of OSO 1. Construction activity will not be conducted using frozen or saturated materials or during periods when significant watershed damage (e.g. rutting, extensive sheet soil erosion, formation of rills/gullies, etc.) is likely to occur. Vegetative debris will not be placed in or under fill embankments.

New road maintenance will include, but is not limited to, blading, ditching, culvert installation and cleanout, gravel surfacing where excessive rutting or erosion may occur and dust control, as necessary to ensure safe operating conditions. All vehicular traffic, personnel movement, construction/restoration operations will be confined to the approved area and to existing roadways and/or access routes.

Snow removal will be conducted on an as-needed basis to accommodate safe travel. Snow removal will occur as necessary throughout the year, as will necessary drainage ditch construction. Removed snow may be stored on permitted well pads to reduce hauling distances and/or at the aerial extent of approved disturbance boundaries to facilitate snow removal for the remainder of the season.

If a county road crossing or encroachment permit is needed, it will be obtained prior to construction.

No new access road is proposed for this well pad - See Topo B.

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 3 of 12

C. Location of Existing Wells:

A) Refer to Topo Map C.

D. Location of Existing and/or Proposed Facilities:

This pad will expand the existing pad for the NBU 194, which is a producing gas well according to Utah Division of Oil, Gas and Mining (UDOGM) records on November 7, 2011. Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee Oil and Gas Onshore LP (Kerr-McGee).

Should the well(s) prove productive, production facilities will be installed on the disturbed portion of each well pad. A berm will be constructed completely around production components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will generally be constructed of compacted subsoil or corrugated metal, and will hold the capacity of the largest tank and have sufficient freeboard to accommodate a 25 year rainfall event. This includes pumping units. Aboveground structures constructed or installed onsite for 6 months or longer, will be painted a flat, non-reflective, earth-tone color chosen at the onsite (typically Shadow Gray). A production facility layout is provided as part of a project-specific APD, ROW or NOS submission.

GAS GATHERING

Please refer to Topo D2- Pad and Pipeline Detail.

The gas gathering pipeline material: Steel line pipe. Surface = Bare pipe. Buried = Coated with fusion bonded epoxy coating (or equivalent). The total gas gathering pipeline distance from the meter to the tie in point is ± 735 ' and the individual segments are broken up as follows:

The following segments will require a ROW to be submitted under a different cover to the Ute Indian Tribe.

±735' (0.1 miles) – Section 22 T9S R21E (SW/4) – On-lease UTU010950A Ute Indian Tribe surface, New 8" buried gas gathering pipeline from the meter to the proposed 16" gas pipleine- ROW in progress. Please refer to Topo D2 - Pad and Pipeline Detail.

LIQUID GATHERING

Please refer to Topo D2- Pad and Pipeline Detail.

The total liquid gathering pipeline distance from the separator to the tie in point is ± 735 ° and the individual segments are broken up as follows:

The following segments will require a ROW to be submitted under a different cover to the Ute Indian Tribe.

±735' (0.1 miles) – Section 22 T9S R21E (SW/4) – On-lease UTU010950A Ute Indian Tribe surface, New 6" buried liquid gathering pipeline from the separator to the proposed 6" liquid pipeline- ROW in progress. Please refer to Topo D2 - Pad and Pipeline Detail.

Pipeline Gathering Construction

Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee. Gas gathering pipeline(s,) gas lift, or liquids pipelines may be constructed to lie on the surface or be buried. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. The area of disturbance during construction from the edge of road or well pad will typically be 30' in width. Where pipelines run cross country, the width of disturbance will typically be 45 ft for buried lines and 30 ft for surface lines. In addition, Kerr-McGee requests for a permanent 30' disturbance width that will be maintained for the portion adjacent to the road. The need for the 30' permanent disturbance width is for maintenance and repairs. Cross country permanent disturbance width also are required to be 30ft.

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 4 of 12

Above-ground installation will generally not require clearing of vegetation or blading of the surface, except where safety considerations necessitate earthwork. In some surface pipeline installation instances pipe cannot be constructed where it will lay. In these cases where an above-ground pipeline is constructed parallel and adjacent to a road, it will be welded/fused on the road and then lifted from the road to the pipeline route. In other cases where a pipeline route is not parallel and adjacent to a road (cross-country between sites), it will be welded/fused in place at a well pad, access road, or designated work area and pulled between connection locations with a suitable piece of equipment.

Buried pipelines will generally be installed parallel and adjacent to existing and/or newly constructed roads and within the permitted disturbance corridor. Buried pipelines may vary from 2 inches (typically fuel gas lines) to 24 inches (typically transportation lines) in diameter, but 6 to 16 inches is typical for a buried gas line. The diameter of liquids pipelines may vary from 2 inches to 12 inches, but 6 inches is the typical diameter. Gas lift lines may vary from 2 to 12 inches in diameter, but 6-inch diameter pipes are generally used for gas lift. If two or more pipelines are present (gas gathering, gas lift, and fluids), they will share a common trench where possible.

Typically, to install a buried pipeline, topsoil will be removed, windrowed and placed on the non-working side of the route for later reclamation. Because working room is limited, the spoil may be spread out across the working side and construction will take place on the spoil. The working side of the corridor will be used for pipe stringing, bending, welding and equipment travel. Small areas on the working side displaying ruts or uneven ground will be groomed to facilitate the safe passage of equipment. After the pipelines are installed, spoil will be placed back into the trench, and the topsoil will be redistributed over the disturbed corridor prior to final reclamation. Typical depth of the trench will be 6 feet, but depths may vary according to site-specific conditions (presence of bedrock, etc.). The proposed trench width for the pipeline would range from 18-48 inches.

The pipeline will be welded along the proposed route and lowered into place. Trenching equipment will cut through the soil or into the bedrock and create good backfill, eliminating the need to remove large rocks. The proposed buried pipeline will be visually and radiographically inspected and the entire pipeline will be pneumatically or hydrostatically tested before being placed into service. Routine vehicle traffic will be prevented from using pipeline routes as travel ways by posting signs at the route's intersection with an access road.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

If pipelines or roads encounter a drainage that could be subject to flooding or surface water during extreme precipitation events, Kerr-McGee will apply all applicable Army Corps mandates as well as the BLM's Hydraulic Considerations for Pipeline Crossings of Stream Channels (BLM Technical Note 423, April 2007). In addition, all stream and drainage crossings will be evaluated to determine the need for stream alteration permits from the State of Utah Division of Water Rights and if necessary, required permits will be secured. Similarly, where a road or pipeline crossing exists the pipe will be butt welded and buried to a depth between 24 and 48 inches or more. Dirt roads will be cut and restored to a condition equivalent to the existing condition. All Uintah County road encroachment and crossing permits, where applicable, will be obtained prior to crossing construction. In no case will pressure testing of pipelines result in discharge of liquids to the surface.

Pipeline signs will be installed along the route to indicate the pipeline proximity, ownership, and to provide emergency contact phone numbers. Above ground valves and lateral T's will be installed at various locations for production integrity and safety purposes.

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 5 of 12

Upon completion of the proposed buried pipeline, the entire area of disturbance will be reclaimed to the standards proposed in the Green River District Reclamation Guidelines. Please refer to section J for more details regarding final reclamation.

When no longer deemed necessary by the operator, Kerr-McGee or it's successor will consult with the Vernal BIA Office before terminating of the use of the pipeline(s).

The Anadarko Completions Transportation System (ACTS) information:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one storage area to be constructed on the drilling pad or a traditional drilling operation with one pit. The storage area will be used to contain only the de-watered drill cuttings and will be lined and reclaimed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit is lined and will be used for the wells drilled on the pad or used as part of our Anadarko Completions Transportation (ACTS) system which is discussed in more detail below. Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completion pit.

If Kerr-McGee does not use a closed loop system, it will construct a drilling reserve pit to contain drill cuttings and for use in completion operations. Depending on the location of the pit, its relation to future drilling locations, the reserve/completion pit will be utilized for the completion of the wells on that pad and/or be used as part of our ACTS system.

Kerr-McGee will use ACTS to optimize the completion processes for multiple pads across the project area which may include up to a section of development. ACTS will facilitate management of frac fluids by utilizing existing reserve pits and temporary, surface-laid aluminum liquids transfer lines between frac locations. The pit will be refurbished as follows when a traditional drill pit is used: mix and pile up drill cuttings with dry dirt, bury the original liner in the pit, walk bottom of pit with cat. Kerr-McGee will reline the pit with a 30 mil liner and double felt padding. The refurbished pit will be the same size or smaller as specified in the originally approved ROW/APD. The pit refurb will be done in a normal procedure and there will be no modification to the pit.

All four sides of the completions pit will be fenced in according to standard pit fencing procedures. Netting will be installed over all pits.

The collected hydrocarbons will be treated and sold at approved sales facilities. A loading rack with drip containment will also be installed where water trucks would unload and load to prevent damage caused from pulling hoses in and out of the pit.

ACTS will require temporarily laying multiple 6" aluminum water transfer lines on the surface between either existing or refurbished reserve pits. The temporary aluminum transfer lines will be utilized to transport frac fluid being injected and/or recovered during the completion process and will be laid adjacent to existing access roads or pipeline corridors. Upon completion of the frac operation, the liquids transfer lines will be flushed with fresh water and purged with compressed air. The contents of the transfer lines will be flushed into a water truck for delivery to another ACTS location or a reserve pit.

The temporary ACTS lines will be permitted under a separate cover to the Ute Indian Tribe.

The volume of frac fluid transported through a water transfer line will vary, but volume is projected to be approximately 1.75 bbls per 50-foot joint. Although the maximum working pressure is 125 psig, the liquids transfer lines will be operated at a pressure of approximately 30 to 40 psig. Kerr-McGee requests to keep the netted pit open for one year from first production of the first produced well on the pad. During this time the surrounding well location completion fluids may be recycled in this pit and utilized for other frac jobs in the area. After one year Kerr-McGee will backfill the pit and reclaim. If the pit is not needed for an entire year it will be backfilled and reclaimed earlier. Kerr-McGee understands that due to the temporary nature of this system, BIA considers this a casual use situation; therefore, no permanent ROW or temporary use plan will need to be issued by the BIA.

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 6 of 12

E. Location and Types of Water Supply:

Water for drilling and completion operations will be obtained from the following sources:

Permit # 49-2307	JD Field Services	Green River- Section 15, T2N, R22E
Permit # 49-2321	R.N. Industries	White River- Section 2, T10S, R24E
Permit # 49-2319	R.N. Industries	White River- Various Sources
Permit # 49-2320	R.N. Industries	Green River- Section 33, T8S, R23E

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

F. Construction Materials:

Construction operations will typically be completed with native materials found on location. Construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source (described in site-specific documents). No construction materials will be removed from Tribal lands without prior approval from the BIA. A source location other than an on-location construction site will be designated either via a map or narrative within the project specific materials provided to the BIA.

G. Methods for Handling Waste:

All wastes subject to regulation will be handled in compliance with applicable laws to minimize the potential for leaks or spills to the environment. Kerr-McGee also maintains a Spill Control and Countermeasure Plan, which includes notification requirements, including the BIA, for all reportable spills of oil, produced liquids, and hazardous materials.

Any accidental release, such as a leak or spill in excess of the reportable quantity, as established by 40 CFR Part 117.3, will be reported as per the requirements of CERCLA, Section 102 B. If a release involves petroleum hydrocarbons or produced liquids, Kerr-McGee will comply with the notification requirements of NTL-3A. Drill cuttings and/or drilling fluids will be contained in the reserve/frac pit whether a closed loop system is used or not. Cuttings will be buried in pit(s) upon closure. Unless specifically approved by the BIA, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface precipitation runoff into the pit (via appropriate placement of subsoil storage areas and/or construction of berms, ditches, etc.). Should unexpected liquid petroleum hydrocarbons (crude oil or condensate) be encountered during drilling, completions or well testing, liquid petroleum hydrocarbons will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by the BIA. Should timely removal not be feasible, the pit will be netted as soon as practical. Similarly, hydrocarbon removal will take place prior to the closure of the pit, unless authorization is provided for disposal via alternate pit closure methods (e.g. solidification).

The reserve and/or fracture stimulation pit will be lined with an impermeable liner. The liner will be a synthetic material 30 mil or thicker. The bottom and side walls of the pit will be void of any sharp rocks that could puncture the liner. The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. After evaporation and when dry, the reserve pit liners will be cut off, ripped and/or folded back (as safety considerations allow) as near to the mud surface as possible and buried on location or hauled to a landfill prior to backfilling the pit with a minimum of five feet of soil material.

Where necessary and if conditions (freeboard, etc.) allow, produced liquids from newly completed wells may be temporarily disposed of into pits for a period not to exceed 90 days as per Onshore Order Number 7 (OSO 7). Subsequently, permanent approved produced water disposal methods will be employed in accordance with OSO 7 and/or as described in a Water Management Plan (WMP). Otherwise, fluids disposal locations and associated haul routes, for ROW consideration, are typically depicted on Topo A of individual projects. Revisions to the water source or method of transportation will be subject to written approval from the BIA.

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 7 of 12

Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after one year from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse (trash and other solid waste including cans, paper, cable, etc.) generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly, and transported to an approved disposal facility. Immediately after removal of the drilling rig, all debris and other waste materials not contained within trash receptacles will be collected and removed from the well location.

For the protection of livestock and wildlife, all open pits (excluding flare pits) will be fenced to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet. Siphons, catchments, and absorbent pads will be installed to keep hydrocarbons produced by the drilling rig or other equipment on location from entering the reserve pit. Hydrocarbons, contaminated pads, and/or soils will be disposed of in accordance with state and federal requirements.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Materials Management

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Hazardous materials may be contained in some grease or lubricants, solvents, acids, paint, and herbicides, among others as defined above. Kerr-McGee maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances that are used during the course of construction, drilling, completion, and production operations for this project. The transport, use, storage and handling of hazardous materials will follow procedures specified by federal and state regulations. Transportation of hazardous materials to the well location is regulated by the Department of Transportation (DOT) under 49 CFR, Parts 171-180. DOT regulations pertain to the packing, container handling, labeling, vehicle placarding, and other safety aspects.

Potentially hazardous materials used in the development or operation of wells will be kept in limited quantities on well sites and at the production facilities for short periods of time. Chemicals meeting the criteria for being an acutely hazardous material/substance or meet the quantities criteria per BLM Instruction Memorandum No. 93-344 will not be used.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities (crude oil/condensate, produced water). They may also be kept in limited quantities on drilling sites (barite, diesel fuel, cement, cottonseed hulls etc.) for short periods of time during drilling or completion activities.

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 8 of 12

Fluids disposal and pipeline/haul routes are depicted on Topo Map A.

Any produced water separated from recoverable condensate from the proposed well will be contained in a water tank and will then be transported by pipeline and/or truck to one of the pre-approved disposal sites:

RNI in Sec. 5 T9S R22E NBU #159 in Sec. 35 T9S R21E Ace Oilfield in Sec. 2 T6S R20E MC&MC in Sec. 12 T6S R19E Pipeline Facility in Sec. 36 T9S R20E

Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E

Bonanza Evaporation Pond in Sec. 2 T10S R23E

Or to one of the following Kerr-McGee active Salt Water Disposal (SWD) wells:

NBU 159 SWD in Sec. 35 T9S R21E CIGE 112D SWD in Sec. 19 T9S R21E CIGE 114 SWD in Sec. 34 T9S R21E NBU 921-34K SWD in Sec. 34 T9S R21E NBU 921-33F SWD in Sec. 34 T9S R21E

H. Ancillary Facilities:

ancillary facilities are

I. Well Site Layout:

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit (for closed loop or non-closed loop operations), access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project, where applicable. Site-specific conditions may require slight deviation in actual equipment depending on whether a closed loop system is used. Surface distance may be less if using closed loop. But in either case, the area of disturbance will not exceed the maximum disturbance outlined in the attached exhibits.

For the protection of livestock and wildlife, all open pits and cellars will be fenced to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Each well will utilize either a centralized tank battery, centralized fluids management system, or have tanks installed on its pad. Production/ Produced Liquid tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks will be kept reasonably free from surface accumulations of liquid hydrocarbons. The tanks are not to be used for disposal of liquids from additional sources without prior approval of BIA.

J. Plans for Surface Reclamation:

The surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. Interim reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

RECEIVED: April 24, 2012

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 9 of 12

Reclamation activities in both phases may include but is not limited to the re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

Interim Reclamation

Interim reclamation may include pit evaporation, fluid removal, pit solidification, re-contouring, ripping, spreading top soil, seeding, and/or weed control. Interim reclamation will be performed in accordance with OSO 1, or written notification will be provided to the BIA for approval. Where feasible, drilling locations, reserve pits, or access routes not utilized for production operations will be re-contoured to a natural appearance.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit. Disposal of pit fluids and linings is discussed in Section G.

Final Reclamation

Final reclamation will be performed for unproductive wells and after the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by Kerr-McGee. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. The BIA will be notified prior to commencement of reclamation operations. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring the site to the approximate contour that existed prior to pad construction, final grading will be conducted over the entire surface of the well site and access road. The area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers, where practical. The surface soil material will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep, where practical. The entire area will be uniformly covered with the depressions constructed perpendicular to the natural flow of water.

Reclamation of roads will be performed at the discretion of the BIA/Tribe. All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded in accordance with the seeding specifications as proposed below in "Measures Common to Interim and Final Reclamation".

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to the BIA/Tribe.

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 10 of 12

Measures Common to Interim and Final Reclamation

Soil preparation will be conducted using a disk for areas in need of more soil preparation following site preparation. This will provide primary soil tillage to a depth no greater than 6 inches. Prior to reseeding, compacted areas will be scarified by ripping or chiseling to loosen compacted soils, promote water infiltration, and improve soil aeration and root penetration.

Seeding will occur year-round as conditions allow and will typically be accomplished through the use of a no-till rangeland style seed drill with a "picker box" in order to seed "fluffy" seed. Where drill seeding is not the preferred method, seed will be broadcast and then raked into the ground at double the rate of drill seeding. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for re-vegetation. The seed mixes will be selected from a list provided by or approved by the BIA/Tribe or a specific seed mix will be proposed by Kerr-McGee to the BIA/Tribe and used after its approval. The selected specific seed mix for each well location and road segment will be utilized while performing interim and final reclamation for each project. All seed will be certified and tags will be maintained by Kerr-McGee. Every effort will be made to obtain "cheat grass free seed".

Seed Mix to be used for Well Site, Access Road, and Pipeline (as applicable):

Indian Ricegrass (Nezpar)	3
Sandberg Bluegrass	0.75
Bottlebrush Squirreltail	1
Great Basin Wildrye	0.5
Crested Wheatgrass	1.5
Winterfat	0.25
Shadscale	1.5
Four-wing Saltbrush	0.75
Forage Kochia	0.25
Total	9.5

Additional soil amendments and/or stabilization may be required on sites with poor soils and/or excessive erosion potential. Where severe erosion can become a problem and/or the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. Slopes will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to: erosion control blankets, hydro-mulch, and/or bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Weed Control

Noxious weeds will be controlled in akk orihect areas un accordance with all applicable rules and regulations.

K. Surface/Mineral Ownership:

Ute Indian Tribe P.O. Box 70 988 South 7500 East Annex Building Fort Duschesne, UT 84026 (435) 722-4307 United States of America Bureau of Land Management 170 South 500 East Vernal, UT 84078 (435) 781-4400 NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 11 of 12

L. Other Information:

Onsite Specifics:

- Rip Rap around corner #10, side #1, corner #2 and side #3 for erosion protection.
- Arch, Paleo and Energy and Minerals monitoring during construction

Cultural and Paleontological Resources

All personnel are strictly prohibited from collecting artifacts, any paleontological specimens or fossils, and from disturbing any significant cultural resources in the area. If artifacts, fossils, or any culturally sensitive materials are exposed or identified in the area of construction, all construction operations that would affect the newly discovered resource will cease, and Kerr-McGee will provide immediate notification to the BIA.

Resource Reports:

A Class I literature survey was completed in December, 2011 by Montgomery Archaeological Consultants, Inc (MOAC). For additional details please refer to report MOAC 11-406.

A paleontological reconnaissance survey was completed on August 12, 2010 by SWCA Environmental Consultants. For additional details please refer to report UT11-14314-119.

Biological field survey was completed on August 8 and 16, 2011 by Grasslands Consulting, Inc (GCI). For additional details please refer to report GCI-570.

Proposed Action Annual Emissions Tables:

Table 1: Proposed Action Annual Emissions (tons/year) ¹						
Pollutant	Development	Production	Total			
NOx	3.8	0.12	3.92			
CO	2.2	0.11	2.31			
VOC	0.1	4.9	5			
SO_2	0.005	0.0043	0.0093			
PM_{10}	1.7	0.11	1.81			
PM _{2.5}	0.4	0.025	0.425			
Benzene	2.2E-03	0.044	0.046			
Toluene	1.6E-03	0.103	0.105			
Ethylbenzene	3.4E-04	0.005	0.005			
Xylene	1.1E-03	0.076	0.077			
n-Hexane	1.7E-04	0.145	0.145			
Formaldehyde	1.3E-02	8.64E-05	1.31E-02			

¹ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison							
		2012 Uintah Basin	Percentage of				
	Proposed Action	Emission	Proposed Action				
	Production Emissions	Inventory ^a	to WRAP Phase				
Species	(ton/yr)	(ton/yr)	III				
NOx	23.52	16,547	0.14%				
VOC	30	127,495	0.02%				

 $[^]a\ http://www.wrapair.org/forums/ogwg/Phase III_Inventory.html$

Uintah Basin Data

NBU 921-22F3DS/ 921-22F4CS/ 921-22K2AS NBU 921-22K4CS/ 921-22N1BS/ 921-22N1CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22K Pad Surface Use Plan of Operations 12 of 12

M. Lessee's or Operators' Representative & Certification:

Laura Abrams Regulatory Analyst II Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6356 Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Laura Abrams December 20, 2011
Date



Kerr-McGee Oil & Gas Onshore LP PO Box 173779 DENVER, CO 80217-3779

October 10, 2011

Ms. Diana Mason Division of Oil, Gas and Mining P.O. Box 145801 Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11

NBU 921-22K4CS

T9S-R21E

Section 22 NESW (Surface and Bottom Hole)

Surface: 1753' FSL, 1640' FWL Bottom Hole: 1576' FSL, 2147' FWL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling.

- Kerr-McGee's NBU 921-22K4CS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing roads and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire directional well bore.


Therefore, based on the above stated information, Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Joe Matney Sr. Staff Landman

for matures



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office P.O. Box 45155 Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

May 14, 2012

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2012 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2012 within the Natural Buttes Unit, Uintah County, Utah.

BHL Sec 22 T09S R21E 0579 FNL 1819 FEL

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

WELL PAD - NBU 921-22K 43-047-52550 NBU 921-22K2AS Sec 22 T09S R21E 1748 FSL 1611 FWL BHL Sec 22 T09S R21E 2366 FSL 1832 FWL 43-047-52551 NBU 921-22K4CS Sec 22 T09S R21E 1753 FSL 1640 FWL BHL Sec 22 T09S R21E 1576 FSL 2147 FWL 43-047-52552 NBU 921-22N1BS Sec 22 T09S R21E 1751 FSL 1630 FWL BHL Sec 22 T09S R21E 1244 FSL 2147 FWL 43-047-52575 NBU 921-22F4CS Sec 22 T09S R21E 1755 FSL 1650 FWL BHL Sec 22 T09S R21E 2406 FNL 2148 FWL 43-047-52576 NBU 921-22F3DS Sec 22 T09S R21E 1747 FSL 1601 FWL BHL Sec 22 T09S R21E 2634 FNL 1870 FWL 43-047-52580 NBU 921-22N1CS Sec 22 T09S R21E 1750 FSL 1620 FWL BHL Sec 22 T09S R21E 0912 FSL 2146 FWL WELL PAD - NBU 921-22B 43-047-52553 NBU 921-22G1CS Sec 22 T09S R21E 0973 FNL 1861 FEL BHL Sec 22 T09S R21E 1574 FNL 1818 FEL 43-047-52554 NBU 921-22B4CS Sec 22 T09S R21E 0965 FNL 1854 FEL BHL Sec 22 T09S R21E 1243 FNL 1819 FEL 43-047-52555 NBU 921-22B4BS Sec 22 T09S R21E 0935 FNL 1828 FEL BHL Sec 22 T09S R21E 0911 FNL 1819 FEL 43-047-52556 NBU 921-22B1CS Sec 22 T09S R21E 0950 FNL 1841 FEL

RECEIVED: May 15, 2012

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

43-047-52557 NBU 921-22B1BS Sec 22 T09S R21E 0958 FNL 1848 FEL

BHL Sec 22 T09S R21E 0249 FNL 1819 FEL

43-047-52607 NBU 921-22A1S Sec 22 T09S R21E 0943 FNL 1835 FEL

BHL Sec 22 T09S R21E 0386 FNL 0464 FEL

WELL PAD - NBU 921-22C

43-047-52558 NBU 921-22C1BS Sec 22 T09S R21E 0691 FNL 2010 FWL

BHL Sec 22 T09S R21E 0085 FNL 2150 FWL

43-047-52567 NBU 921-22C4CS Sec 22 T09S R21E 0696 FNL 2001 FWL

BHL Sec 22 T09S R21E 1078 FNL 2149 FWL

43-047-52569 NBU 921-22F1BS Sec 22 T09S R21E 0701 FNL 1993 FWL

BHL Sec 22 T09S R21E 1410 FNL 2149 FWL

43-047-52570 NBU 921-22F1CS Sec 22 T09S R21E 0707 FNL 1984 FWL

BHL Sec 22 T09S R21E 1742 FNL 2149 FWL

43-047-52571 NBU 921-22F4BS Sec 22 T09S R21E 0712 FNL 1976 FWL

BHL Sec 22 T09S R21E 2073 FNL 2149 FWL

WELL PAD - NBU 921-22I

43-047-52560 NBU 921-22I1CS Sec 22 T09S R21E 1973 FSL 0620 FEL

BHL Sec 22 T09S R21E 2237 FSL 0494 FEL

43-047-52561 NBU 921-22I1BS Sec 22 T09S R21E 1981 FSL 0626 FEL

BHL Sec 22 T09S R21E 2569 FSL 0494 FEL

43-047-52562 NBU 921-22G4CS Sec 22 T09S R21E 2013 FSL 0650 FEL

BHL Sec 22 T09S R21E 2569 FNL 1818 FEL

43-047-52564 NBU 921-22J4CS Sec 22 T09S R21E 1989 FSL 0632 FEL

BHL Sec 22 T09S R21E 1410 FSL 1817 FEL

43-047-52565 NBU 921-22J4AS Sec 22 T09S R21E 1997 FSL 0638 FEL

BHL Sec 22 T09S R21E 1796 FSL 1580 FEL

43-047-52566 NBU 921-22J1BS Sec 22 T09S R21E 2005 FSL 0644 FEL

BHL Sec 22 T09S R21E 2405 FSL 1817 FEL

WELL PAD - NBU 921-22H

43-047-52563 NBU 921-22H4CS Sec 22 T09S R21E 2196 FNL 0627 FEL

BHL Sec 22 T09S R21E 2403 FNL 0494 FEL

43-047-52650 NBU 921-22H1CS Sec 22 T09S R21E 2179 FNL 0637 FEL

BHL Sec 22 T09S R21E 1740 FNL 0494 FEL

43-047-52651 NBU 921-22A4CS Sec 22 T09S R21E 2170 FNL 0642 FEL

BHL Sec 22 T09S R21E 1288 FNL 0504 FEL

43-047-52652 NBU 921-22A4BS Sec 22 T09S R21E 2162 FNL 0647 FEL

BHL Sec 22 T09S R21E 0670 FNL 0494 FEL

43-047-52653 NBU 921-22H4BS Sec 22 T09S R21E 2188 FNL 0632 FEL

BHL Sec 22 T09S R21E 2071 FNL 0494 FEL

Page 2

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

WELL PAD - NBU 921-22E

43-047-52568 NBU 921-22E4BS Sec 22 T09S R21E 2179 FNL 0750 FWL

BHL Sec 22 T09S R21E 2239 FNL 0824 FWL

43-047-52572 NBU 921-22E1BS Sec 22 T09S R21E 2179 FNL 0720 FWL

BHL Sec 22 T09S R21E 1576 FNL 0824 FWL

43-047-52573 NBU 921-22E1CS Sec 22 T09S R21E 2179 FNL 0730 FWL

BHL Sec 22 T09S R21E 1908 FNL 0824 FWL

43-047-52574 NBU 921-22E4CS Sec 22 T09S R21E 2179 FNL 0740 FWL

BHL Sec 22 T09S R21E 2572 FNL 0824 FWL

WELL PAD - NBU 921-22L

43-047-52577 NBU 921-22K2DS Sec 22 T09S R21E 1668 FSL 0666 FWL

BHL Sec 22 T09S R21E 2038 FSL 1784 FWL

43-047-52582 NBU 921-22L1BS Sec 22 T09S R21E 1660 FSL 0648 FWL

BHL Sec 22 T09S R21E 2408 FSL 0824 FWL

43-047-52583 NBU 921-22L4BS Sec 22 T09S R21E 1672 FSL 0675 FWL

BHL Sec 22 T09S R21E 1744 FSL 0824 FWL

43-047-52585 NBU 921-22L1CS Sec 22 T09S R21E 1664 FSL 0657 FWL

BHL Sec 22 T09S R21E 2076 FSL 0824 FWL

WELL PAD - NBU 921-220

43-047-52578 NBU 921-2204CS Sec 22 T09S R21E 0269 FSL 1655 FEL

BHL Sec 22 T09S R21E 0086 FSL 1816 FEL

43-047-52579 NBU 921-22P4BS Sec 22 T09S R21E 0280 FSL 1606 FEL

BHL Sec 22 T09S R21E 0581 FSL 0494 FEL

43-047-52581 NBU 921-22P4CS Sec 22 T09S R21E 0278 FSL 1616 FEL

BHL Sec 22 T09S R21E 0251 FSL 0494 FEL

43-047-52590 NBU 921-2204BS Sec 22 T09S R21E 0271 FSL 1645 FEL

BHL Sec 22 T09S R21E 0416 FSL 1816 FEL

43-047-52612 NBU 921-2201BS Sec 22 T09S R21E 0276 FSL 1625 FEL

BHL Sec 22 T09S R21E 1079 FSL 1817 FEL

43-047-52613 NBU 921-2201CS Sec 22 T09S R21E 0274 FSL 1635 FEL

BHL Sec 22 T09S R21E 0747 FSL 1816 FEL

WELL PAD - NBU 921-22M

43-047-52586 NBU 921-22M1BS Sec 22 T09S R21E 0695 FSL 0660 FWL

BHL Sec 22 T09S R21E 1080 FSL 0823 FWL

43-047-52587 NBU 921-22M1CS Sec 22 T09S R21E 0686 FSL 0654 FWL

BHL Sec 22 T09S R21E 0748 FSL 0823 FWL

43-047-52588 NBU 921-22M4BS Sec 22 T09S R21E 0678 FSL 0649 FWL

BHL Sec 22 T09S R21E 0416 FSL 0823 FWL

43-047-52589 NBU 921-22M4CS Sec 22 T09S R21E 0670 FSL 6043 FWL

BHL Sec 22 T09S R21E 0086 FSL 0823 FWL

Page 3

Page 4

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L Coulthard

Disc. cn=Michael L. Coulthard, o=Bureau of Land Management,
ou=Branch of Minerals, email-Michael_Coulthard@blm.gov, c=US
Date: 2012.05.15 07:17:01 -06'00'

bcc: File - Natural Buttes Unit Division of Oil Gas and Mining Central Files

Agr. Sec. Chron Fluid Chron

MCoulthard:mc:5-14-12

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 5/1/2012 API NO. ASSIGNED: 43047525510000

WELL NAME: NBU 921-22K4CS

OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) PHONE NUMBER: 720 929-6356

CONTACT: Laura Abrams

PROPOSED LOCATION: NESW 22 090S 210E **Permit Tech Review:**

> SURFACE: 1753 FSL 1640 FWL **Engineering Review:**

> **BOTTOM: 1576 FSL 2147 FWL** Geology Review:

COUNTY: UINTAH

LATITUDE: 40.01906 LONGITUDE: -109.54140 UTM SURF EASTINGS: 624473.00 NORTHINGS: 4430891.00

FIELD NAME: NATURAL BUTTES LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU 010950-A PROPOSED PRODUCING FORMATION(S): BLACKHAWK

SURFACE OWNER: 2 - Indian **COALBED METHANE: NO**

RECEIVED AND/OR REVIEWED: LOCATION AND SITING: ✓ PLAT R649-2-3.

Unit: NATURAL BUTTES Bond: FEDERAL - WYB000291

Potash R649-3-2. General

Oil Shale 190-5

Oil Shale 190-3 R649-3-3. Exception

Oil Shale 190-13 **Drilling Unit**

Board Cause No: Cause 173-14 Water Permit: 43-8496

Effective Date: 12/2/1999 **RDCC Review:**

Siting: Suspends General Siting Fee Surface Agreement


✓ Intent to Commingle R649-3-11. Directional Drill

Commingling Approved

Comments: Presite Completed

Stipulations:

3 - Commingling - ddoucet 4 - Federal Approval - dmason 15 - Directional - dmason 17 - Oil Shale 190-5(b) - dmason



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: NBU 921-22K4CS API Well Number: 43047525510000 Lease Number: UTU 010950-A

Surface Owner: INDIAN Approval Date: 5/30/2012

Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the BLACKHAWK Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Commingle:

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil

shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

• Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at http://oilgas.ogm.utah.gov

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
 - Requests to Change Plans (Form 9) due prior to implementation
 - Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
 - Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Approved By:

For John Rogers Associate Director, Oil & Gas Form 3160-3 RECEIVED (August 2007)

RECEIVEL

FORM APPROVED OMB No. 1004-0136 Expires July 31, 2010

UNITED STATES

CAS SUPPARTMENT OF THE INTERIOR JAN 1 0 2012

OF OIL OF OIL OF OIL OF LAND MANAGEMENT

MAPPLICATION FOR PERMIT TO DELLE REPORTER 2

5. Lease Serial No. UTU010950A

			DEIVI,"	vemai Utan	o. It indian, rinotac of Tibe Name	5
la. Type of Work:	⊠ DRILL	REENTER			7. If Unit or CA Agreement, Name UTU63047A	and No.
1b. Type of Well:	Oil Well	☑ Gas Well ☐ Ot		gle Zone	8. Lease Name and Well No. NBU 921-22K4CS	
· · · · · · · · · · · · · · · · · · ·		Contact: ONSHOR⊞MaiPLaura.A	LAURA ABRAMS brams@anadarko.com		9. API Well No. 43.04152551	
3a. Address PO BOX 173779 DENVER, CO 8			3b. Phone No. (inclu Ph: 720-929-635 Fx: 720-929-735	6	10. Field and Pool, or Exploratory NATURAL BUTTES	***************************************
4. Location of Well	(Report locati	on clearly and in accorde	ance with any State requ	irements.*)	11. Sec., T., R., M., or Blk. and Sur	vey or Area
At surface	NESW	/ 1753FSL 1640FWL	. 40.019132 N Lat,	109.541467 W Lon	Sec 22 T9S R21E Mer SLI	В
		/ 1576FSL 2147FWL		109.539662 W Lon		_
14. Distance in mile APPROXIMA	s and direction fi FELY 43.8 MI	rom nearest town or post LES SOUTH OF VE	office* RNAL, UT		12. County or Parish UINTAH	13. State UT
15. Distance from prolease line, ft. (A	roposed location	to nearest property or ig. unit line, if any)	16. No. of Acres in L	ease	17. Spacing Unit dedicated to this v	vell
1,071'		ig. unit inic, it uny)	800.00			
18. Distance from processing completed appl	roposed location	to nearest well, drilling,	19. Proposed Depth		20. BLM/BIA Bond No. on file	
completed, applied for, on this lease, ft.		11132 MD 11084 TVD		WYB000291		
21. Elevations (Show whether DF, KB, RT, GL, etc. 4888 GL 22. Approximate date work will start 06/30/2012			23. Estimated duration 60-90 DAYS			
			24. Att	achments		
he following, comple	ted in accordance	e with the requirements o	f Onshore Oil and Gas O	order No. 1, shall be attached to the	his form:	
Well plat certified b A Drilling Plan. A Surface Use Plan SUPO shall be file	(if the location i	rveyor. s on National Forest Syst opriate Forest Service Of	em Lands, the fice).	1tem 20 above). 5. Operator certification	ns unless covered by an existing bond	•
25 0:				L		

Title Assistant Field Manager Lands & Mineral Resources	VERNAL FIELD OFFICE	
Approved by (Signature)	Name (Printed/Typed) Jerry Kenczka	^D JÜN 1 2 201
Title REGULATORY ANALYST II		
25. Signature (Electronic Submission)	Name (Printed/Typed) LAURA ABRAMS Ph: 720-929-6356	Date 12/20/2011

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #126382 verified by the BLM Well Information System For KERR MCGEE OIL&GAS ONSHORE, LP, sent to the Vernal

NOTICE OF APPROVAL CONDITIONS OF APPROVAL ATTACHED

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED

171BR1184A9



UNITED STATES DEPARTMENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT VERNAL FIELD OFFICE** 170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company:	Kerr McGee Oil & Gas Onshore LP	Location:	NESW, Sec.22,T9S R21E
Well No:	NBU 921-22K4CS	Lease No:	UTU-010950A
API No:	43-047-52551	Agreement:	Natural Buttes

OFFICE NUMBER:

(435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR FIELD REPRESENTATIVE TO INSURE COMPLIANCE

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.

NOTIFICATION REQUIREMENTS

Construction Activity (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	-	The Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist shall be notified at least 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.
Construction Completion (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	-	Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion. Notify the BLM Environmental Scientist prior to moving on the drilling rig.
Spud Notice (Notify BLM Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify BLM Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: blm.ut vn opreport@blm.gov
BOP & Related Equipment Tests (Notify BLM Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify BLM Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

Page 2 of 7 Well: NBU 921-22K4CS 6/8/2012

SURFACE USE PROGRAM CONDITIONS OF APPROVAL (COAs)

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.

Site Specific COA's

- Paint facilities "Shadow Gray".
- Conduct a raptor survey prior to construction operation if such activates would take place during raptor nesting season (January 1- September 30). If active raptor nests are identified during the survey, operations should be conducted according to the seasonal restrictions detailed in the Uinta Basin-specific RMP guidelines and spatial offsets specified by the USFWS Utah.
- If construction and/or drilling operations have not been initiated prior to August 8, 2012, conduct
 a biological survey to determine the guidelines specified in the USFWS Rare Plant Conservation
 Measures and the BLM RMP ROD. KMG will implement commitment contained in the GNB BO.
- Monitor construction operation with a permitted archaeologist.
- Monitor construction operation with a permitted paleontologist.
- Monitor construction operations with Ute Energy and Minerals technician.
- Riprap corners #2 and #10 and sides #1 and #3 for erosion protection.

Pipeline Route from North Compressor to West Cottonwood Compressor

- If construction and/or drilling operations have not been initiated prior to August 8, 2012, conduct
 a biological survey to determine the guidelines specified in the USFWS Rare Plant Conservation
 Measures and the BLM RMP ROD. KMG will implement commitment contained in the GNB BO.
- Monitor areas with a permitted paleontologist where pipeline travels through Sections 15, 16,
 17, and 22. Monitor section 27 at the beginning of construction and spot monitor thereafter.

ACTS line

- If construction and/or drilling operations have not been initiated prior to August 8, 2012, conduct
 a biological survey to determine the guidelines specified in the USFWS Rare Plant Conservation
 Measures and the BLM RMP ROD. KMG will implement commitment contained in the GNB BO.
- Monitor areas with a permitted paleontologist where ACTS line travels through Section 15 SWSE, and Section 22 NWNE, NENW, SWSW, and SWSE.

Page 3 of 7 Well: NBU 921-22K4CS 6/8/2012

DOWNHOLE PROGRAM CONDITIONS OF APPROVAL (COAs)

SITE SPECIFIC DOWNHOLE COAs:

- A copy of Kerr McGee's Standard Operating Practices (SOP version: dated 7/17/08 and approved 7/28/08) shall be on location.
- Surface casing cement shall be brought to surface.
- Production casing cement shall be brought 200' up and into the surface casing.
- Electronic/mechanical mud monitoring equipment shall be required, from surface casing shoe to TD, which shall include as a minimum: pit volume totalizer (PVT); stroke counter; and flow sensor.

Page 4 of 7 Well: NBU 921-22K4CS 6/8/2012

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the
 daily drilling report. Components shall be operated and tested as required by Onshore Oil &
 Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be
 performed by a test pump with a chart recorder and NOT by the rig pumps. Test shall be
 reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- Cement baskets shall not be run on surface casing.
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water
 is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM
 Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.

Page 5 of 7 Well: NBU 921-22K4CS 6/8/2012

- A cement bond log (CBL) will be run from the production casing shoe to the <u>top of cement</u> and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- Please submit an electronic copy of all other logs run on this well in LAS format to BLM_UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

Page 6 of 7 Well: NBU 921-22K4CS 6/8/2012

OPERATING REQUIREMENT REMINDERS:

 All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.

- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be
 notified when it is placed in a producing status. Such notification will be by written
 communication and must be received in this office by not later than the fifth business day
 following the date on which the well is placed on production. The notification shall provide, as a
 minimum, the following informational items:
 - o Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - o Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if

Page 7 of 7 Weil: NBU 921-22K4CS 6/8/2012

performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field
 Office Petroleum Engineers will be provided with a date and time for the initial meter calibration
 and all future meter proving schedules. A copy of the meter calibration reports shall be
 submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API
 standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All
 measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted
 to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs
 first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be
 adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively
 sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover
 equipment shall be removed from a well to be placed in a suspended status without prior
 approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30
 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given
 before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

Sundry Number: 32579 API Well Number: 43047525510000

	STATE OF UTAH		FORM 9
ι	DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MIN		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A
SUNDR	Y NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In
	posals to drill new wells, significantly reenter plugged wells, or to drill horizon for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-22K4CS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047525510000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	n Street, Suite 600, Denver, CO, 8021	PHONE NUMBER: 720 929-	9. FIELD and POOL or WILDCAT: 65NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1753 FSL 1640 FWL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Merio	dian: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
✓ SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud: 11/28/2012	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
11/20/2012	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
	WILDCAT WELL DETERMINATION	OTHER	OTHER:
44 DECORIDE BRODOCED OR		all martiness details in chading details	<u> </u>
MIRU TRIPLE A BU RAN 14" 36.7# SC	COMPLETED OPERATIONS. Clearly show CKET RIG. DRILLED 20" CON HEDULE 10 CONDUCTOR PIC. SPUD WELL LOCATION ON 09:30 HRS.	IDUCTOR HOLE TO 40'. PE. CEMENT WITH 28	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY December 03, 2012
NAME (PLEASE PRINT) Lindsey Frazier	PHONE NUME 720 929-6857	BER TITLE Regulatory Analyst II	
SIGNATURE N/A		DATE 12/3/2012	

SUBMIT AS EMAIL

Print Form

BLM - Vernal Field Office - Notification Form

Operator KERR-McGEE OIL & GAS Rig Name/# BUCKET RIG
Submitted By L. Urban Phone Number 720.929.6501
Well Name/Number NBU 921-22K4CS
Qtr/Qtr NE/SW Section 22 Township 9s Range 21E
Lease Serial Number UTU 010950-A
API Number 4304752551
<u>Spud Notice</u> – Spud is the initial spudding of the well, not drilling out below a casing string.
Date/Time <u>11/28/2012</u> <u>13:00 HRS</u> AM ☐ PM ✓
Casing — Please report time casing run starts, not cementing times. ✓ Surface Casing Intermediate Casing Production Casing Liner Other
Date/Time <u>12/17/2012</u> <u>08:00 HRS</u> AM ✓ PM ☐
BOPE Initial BOPE test at surface casing point BOPE test at intermediate casing point 30 day BOPE test Other RECEIVED NOV 2 7 2012 DIV. OF OIL, GAS & MINING Other
Date/Time AM
Remarks ESTIMATED DATE AND TIME. PLEASE CONTACT KENNY GATHINGS AT

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

ENTITY ACTION FORM

Operator:

KERR McGEE OIL & GAS ONSHORE LP

Operator Account Number: N

Address:

P.O. Box 173779

city DENVER

state CO

Phone Number: (720) 929-6857

Well 1

API Number	Well	Name	QQ Sec Twp		Rng County		
4304752575	NBU 921-22F4CS	NBU 921-22F4CS		22	98	21E UINTAH	
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
В	99999	3900	1	1/28/20 ⁻	12	12/1	013013

Comments:

MIRU TRIPLE A BUCKET RIG.

SPUD WELL LOCATION ON NOVEMBER 28, 2012 AT 07:00 HRS. BHI . SCNW

zip 80217

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County	
4304752551	NBU 921-22K4CS		NESW	22	98	21E	UINTAH	
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date			
B	99999	2900	1	1/28/20	12	12/	1019013	

Comments:

MIRU TRIPLE A BUCKET RIG.

Maund

SPUD WELL LOCATION ON NOVEMBER 28, 2012 AT 09:30 HRS. BHL: nesu

Well 3

API Number	Well	Name	QQ	Sec	Twp	Rng	County
4304752552	NBU 921-22N1E	ss	NESW	22	98	21E	UINTAH
Action Code	Current Entity Number	New Entity Number	s	pud Da	te .		y Assignment fective Date
B	99999	3900	1	1/28/20	12	1a/	10/9019

Comments:

MIRU TRIPLE A BUCKET RIG.

WSMVD

SPUD WELL LOCATION ON NOVEMBER 28, 2012 AT 12:00 HRS. BHL: Sesu

ACTION CODES:

- A Establish new entity for new well (single well only)
- B Add new well to existing entity (group or unit well)
- C Re-assign well from one existing entity to Re-Entity to
- Re-assign well from one existing entity to a new entity
- E Other (Explain in 'comments' section)

DEC 05 2012

Lindsey Frazier

Name (Please Print)

Signature

REGULATORY ANALYST II

12/3/2012

Title

Date

Sundry Number: 34792 API Well Number: 43047525510000 FEDERAL APPROVAL OF THIS ACTION IS NECESSARY

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reepter plugged wells, or to drill horizontal laterals. Use APPLICATION 7.UNIT or CA AGREEMENT NAME:				FORM 9	
DIVISION OF OIL, GAS, AND MINING SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reepter plugged wells, or to drill horizontal laterals. Use APPLICATION 7.UNIT or CA AGREEMENT NAME:					
Do not use this form for proposals to drill new wells, significantly deepen existing wells below Current bottom-hole depth, reepter plugged wells, or to drill horizontal laterals. Use APPLICATION 7.UNIT or CA AGREEMENT NAME:				5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A	
current bottom-hole depth, reenter plugged wells, or to drill borizontal laterals, Use APPLICATION 7.UNIT or CA AGREEMENT NAME:	SUNDRY NOTICES AND REPORTS ON WELLS			·	
FOR PERMIT TO DRILL form for such proposals.	current bottom-hole depth,	lepth, reenter plugged wells, or to drill horizo		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES	
1. TYPE OF WELL Gas Well 8. WELL NAME and NUMBER: NBU 921-22K4CS	· -			1 1 1	
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. 9. API NUMBER: 43047525510000				'	
3. ADDRESS OF OPERATOR: PHONE NUMBER: 9. FIELD and POOL or WILDCAT: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779 720 929-6 5NL&TUERAL BUTTES					
4. LOCATION OF WELL FOOTAGES AT SURFACE: UINTAH	FOOTAGES AT SURFACE:				
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 22 Township: 09.0S Range: 21.0E Meridian: S UTAH	QTR/QTR, SECTION, TOWNS	OWNSHIP, RANGE, MERIDIAN:	dian: S	1 -	
CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA	11. CHEC	CHECK APPROPRIATE BOXES TO INDICAT	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA	
TYPE OF SUBMISSION TYPE OF ACTION	TYPE OF SUBMISSION	ON	TYPE OF ACTION		
_ ACIDIZE ALTER CASING CASING REPAIR	_	ACIDIZE	ALTER CASING	CASING REPAIR	
NOTICE OF INTENT Approximate date work will start: CHANGE TO PREVIOUS PLANS CHANGE TUBING CHANGE WELL NAME		start: CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME	
2/15/2013	2/15/2013	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE	
SUBSEQUENT REPORT DEEPEN FRACTURE TREAT NEW CONSTRUCTION	SUBSEQUENT REPORT			NEW CONSTRUCTION	
Date of Work Completion: OPERATOR CHANGE		: _			
PRODUCTION START OR RESUME RECLAMATION OF WELL SITE RECOMPLETE DIFFERENT FORMATION					
L SPUD REPORT					
Date of Spud:	Date or Spud:				
☐ ☐ TUBING REPAIR ☐ VENT OR FLARE ☐ WATER DISPOSAL		L TUBING REPAIR	☐ VENT OR FLARE	WATER DISPOSAL	
☐ DRILLING REPORT ☐ WATER SHUTOFF ☐ SI TA STATUS EXTENSION ☐ APD EXTENSION Report Date: ☐ Report Date:		WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION	
WILDCAT WELL DETERMINATION ✓ OTHER OTHER: DV Tool		WILDCAT WELL DETERMINATION	✓ OTHER	OTHER: DV Tool	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.	12. DESCRIBE PROPOSED OR	ED OR COMPLETED OPERATIONS. Clearly show a	all pertinent details including dates, o	depths, volumes, etc.	
The operator requests authorization to place a DV tool in the Accepted by the	· ·	•			
production casing string and run a 2 stage cement job after setting the utah Division of Oil, Gas and Mining	ı ·	•			
production casing to ensure cement is properly enculated to surface.	, .				
Below describes how it will be conducted: Run I-80 casing from TD to approximately 4,950 feet where the DV Tool will be placed. Run a	I .		•	Date: February 19, 2013	
centralizer and cement basket on the I-80 joint below the DV Tool (use By:) of K Durf	By: Der () A				
a stop ring to keep the CMT Basket at top of the tool joint). Run a DV					
Tool at approximately 4,950 feet. Run LTC/DXQ crossover. Run a					
centralizer and a cement basket on the Crossover (use a stop ring to					
keep the CMT Basket at bottom of the tool joint). Run DXQ casing to					
surface. The actual depth details will be captured in the well					
completion report.					
NAME (PLEASE PRINT) Lindsey Frazier PHONE NUMBER 720 929-6857 TITLE Regulatory Analyst II		•			
SIGNATURE DATE N/A 2/15/2013	l .				

Sundry Number: 35030 API Well Number: 43047525510000

	STATE OF UTAH		FORM 9		
DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING			5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A		
SUNDRY NOTICES AND REPORTS ON WELLS			6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In		
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.			7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES		
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-22K4CS		
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047525510000		
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl	h Street, Suite 600, Denver, CO, 80217	PHONE NUMBER: 73779 720 929-6	9. FIELD and POOL or WILDCAT: 65NATURAL BUTTES		
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1753 FSL 1640 FWL			COUNTY: UINTAH		
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Merid	lian: S	STATE: UTAH		
11. CHECI	K APPROPRIATE BOXES TO INDICAT	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA		
TYPE OF SUBMISSION		TYPE OF ACTION			
	ACIDIZE	ALTER CASING	CASING REPAIR		
NOTICE OF INTENT	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME		
Approximate date work will start:	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE		
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION		
Date of Work Completion.					
	☐ OPERATOR CHANGE	PLUG AND ABANDON	☐ PLUG BACK		
SPUD REPORT Date of Spud:	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	☐ RECOMPLETE DIFFERENT FORMATION		
	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	L TEMPORARY ABANDON		
/	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL		
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION		
2/24/2013	WILDCAT WELL DETERMINATION	OTHER	OTHER:		
FINISHED DRILLING CASING. RELEASE AND CEMENT WILL E	COMPLETED OPERATIONS. Clearly show as TO 10065' ON 2/22/2013. CESTO H&P 318 RIG ON 2/24/2013. BE INCLUDED WITH THE WELL AITING ON FINAL COMPLETION.	MENTED PRODUCTION B. DETAILS OF CASING COMPLETION REPORT.	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 01, 2013		
NAME (PLEASE PRINT)	PHONE NUMB				
Laura Abrams	720 929-6356	Regulatory Analyst II			
SIGNATURE N/A		DATE 2/26/2013			


Sundry Number: 34693 API Well Number: 43047525510000 FEDERAL APPROVAL OF THIS ACTION IS NECESSARY

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES	S	FORM 9	
	5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A			
SUNDRY NOTICES AND REPORTS ON WELLS			6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In	
Do not use this form for pro current bottom-hole depth, FOR PERMIT TO DRILL form	oposals to drill new wells, significantly de reenter plugged wells, or to drill horizont n for such proposals.	eepen existing wells below al laterals. Use APPLICATION	7.UNIT OF CA AGREEMENT NAME: NATURAL BUTTES	
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-22K4CS	
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	NSHORE, L.P.		9. API NUMBER: 43047525510000	
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl	h Street, Suite 600, Denver, CO, 80217 3	PHONE NUMBER: 720 929-6	9. FIELD and POOL or WILDCAT: 5M&TURAL BUTTES	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1753 FSL 1640 FWL			COUNTY: UINTAH	
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Meridia	n: S	STATE: UTAH	
11. CHEC	K APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPOR	RT, OR OTHER DATA	
TYPE OF SUBMISSION		TYPE OF ACTION		
The operator is refrom a pad, and to the pad based upoperiodic well tests. Well API NBU 921 NBU 921-22K40	COMPLETED OPERATIONS. Clearly show all questing the option to measure allocate gas production to the on multi-phase flow measurem Please see the attached docures and allocate gas production to the control of the cont	re total gas produced ne individual wells on nent at each well and ments. Thank you. Pad '52575 NBU 921-22K NBU 921-22N1BS	CASING REPAIR CHANGE WELL NAME CONVERT WELL TYPE NEW CONSTRUCTION PLUG BACK RECOMPLETE DIFFERENT FORMATION TEMPORARY ABANDON WATER DISPOSAL APD EXTENSION OTHER: Multi-Phase Meter Lepths, volumes, etc. Approved by the Utah Division of Oil, Gas and Mining Date: March 05, 2013 By: Dall Warf	
921-22K NBU	U 921-22K NBU 921-22N1CS 921-22K2AS 4304752550 NE 921-22F3DS 4304752576	BU 921-22K NBU		
NAME (PLEASE PRINT) Lindsey Frazier	PHONE NUMBER 720 929-6857	R TITLE Regulatory Analyst II		
SIGNATURE N/A		DATE 2/13/2013		

Sundry Number: 34693 API Well Number: 43047525510000

The fluids from each well will be measured utilizing a multi-phase flow meter and then directed to a common separator for all wells on the pad. Liquids would be directed to tanks and the gas from all the wells measured through a calibrated orifice meter. The volume of gas measured through this meter, plus fuel gas consumed on location, will be the volume of gas that is produced from the pad. Gas volume for each individual well on the pad will be based on an allocation formula utilizing the total pad volume measured plus fuel gas consumed and the calculated volume from each well utilizing the multi-phase flow meters. The multi-phase flow meter volume calculation will be calibrated by periodic individual well tests.

RECEIVED: Feb. 13, 2013



State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# HP 318 Submitted By BRAD PEDERSEN Phone Number 435- 828-0988 Well Name/Number NBU 921-22K4CS Qtr/Qtr NE/SW Section 22 Township 24E Range 98 Lease Serial Number UTU-010950-A 95 API Number 434=04752551
<u>Casing</u> – Time casing run starts, not cementing times.
Production Casing Other
Date/Time AM PM
BOPE Initial BOPE test at surface casing point Other
Date/Time <u>2/18/2013</u> <u>10:00</u> AM ⊠ PM □
RECEIVED Rig Move Location To: NBU 921-22K4CS RECEIVED FEB 1 7 2013 DIV. OF OIL, GAS & MINING
Date/Time <u>2/18/2013</u> <u>08:00</u> AM ⊠ PM □
Remarks TIME IS ESTIMATED

State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# HP 318 Submitted
By <u>BRAD PEDERSEN</u> Phone Number <u>435-828-0988</u> Well Name/Number <u>NBU 921-22K4CS</u>
Qtr/Qtr NE/SW Section 22 Township 9S Range 21E
Lease Serial Number <u>UTU-010950-A</u>
API Number 4304752551
<u>Casing</u> – Time casing run starts, not cementing times.
Production Casing Other
Date/Time <u>2/23/2013</u> <u>16:00</u> AM ☐ PM ⊠
BOPE
Initial BOPE test at surface casing pointOther
Date/Time AM
RECEIVED FEB 2 3 2013
Location To: DIV. OF OIL, GAS & MINING
Date/Time AM DM PM D
Remarks TIME IS ESTIMATED

State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# HP 318 Submitted
By <u>BRAD PEDERSEN</u> Phone Number <u>435-828-0988</u> Well Name/Number <u>NBU 921-22K4CS</u>
Qtr/Qtr NE/SW Section 22 Township 9S Range 21E
Lease Serial Number <u>UTU-010950-A</u>
API Number 4304752551
<u>Casing</u> – Time casing run starts, not cementing times.
Production Casing Other
Date/Time <u>2/23/2013</u> <u>16:00</u> AM ☐ PM ⊠
BOPE
Initial BOPE test at surface casing pointOther
Date/Time AM
RECEIVED FEB 2 3 2013
Location To: DIV. OF OIL, GAS & MINING
Date/Time AM DM PM D
Remarks TIME IS ESTIMATED

Sundry Number: 36434 API Well Number: 43047525510000

	STATE OF UTAH				FORM 9	
DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING			5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A			
SUNDRY NOTICES AND REPORTS ON WELLS			6. IF INDIAN, ALLO	OTTEE OR TRIBE NAME:		
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.			7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well				8. WELL NAME and NUMBER: NBU 921-22K4CS		
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.			9. API NUMBER: 430475255100	000	
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	n Street, Suite 600, Denver, CO, 802		NE NUMBER: 79 720 929-6	9. FIELD and POOL or WILDCAT: 5NATURAL BUTTES		
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1753 FSL 1640 FWL				COUNTY: UINTAH		
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NESW Section: 2	IIP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Me	ridian:	s	STATE: UTAH		
11. CHECI	K APPROPRIATE BOXES TO INDIC	ATE N	ATURE OF NOTICE, REPOR	T, OR OTHER D	ATA	
TYPE OF SUBMISSION			TYPE OF ACTION			
	ACIDIZE		ALTER CASING	CASING RE	PAIR	
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS		CHANGE TUBING	CHANGE W	ELL NAME	
	CHANGE WELL STATUS		COMMINGLE PRODUCING FORMATIONS	CONVERT V	VELL TYPE	
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	□ F	FRACTURE TREAT	☐ NEW CONS	TRUCTION	
	OPERATOR CHANGE	☐ F	PLUG AND ABANDON	PLUG BACK	(
SPUD REPORT	PRODUCTION START OR RESUME	□ F	RECLAMATION OF WELL SITE	RECOMPLE	TE DIFFERENT FORMATION	
Date of Spud:	REPERFORATE CURRENT FORMATION	П.	SIDETRACK TO REPAIR WELL	TEMPOPAR	RY ABANDON	
	TUBING REPAIR		/ENT OR FLARE	WATER DIS		
✓ DRILLING REPORT						
Report Date: 4/4/2013	WATER SHUTOFF	□ s	SI TA STATUS EXTENSION	☐ APD EXTEN	ISION	
	WILDCAT WELL DETERMINATION		OTHER	OTHER:		
No Activity for	completed operations. Clearly shoot the month of March 2013	. Wel	II TD at 10,065	Accepte Utah D Oil, Gas a	c. ed by the ivision of and Mining CORD ONLY 5, 2013	
NAME (PLEASE PRINT) Luke Urban	PHONE NUN 720 929-6501	IBER	TITLE Regulatory Specialist			
SIGNATURE N/A			DATE 4/4/2013			

Sundry Number: 37430 API Well Number: 43047525510000

	STATE OF UTAH		FORM 9
ı	DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MINI		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A
SUNDR	Y NOTICES AND REPORTS O	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In
	posals to drill new wells, significantly d eenter plugged wells, or to drill horizon n for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-22K4CS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047525510000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	Street, Suite 600, Denver, CO, 80217	PHONE NUMBER: 3779 720 929-6	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1753 FSL 1640 FWL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NESW Section: 2	IIP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Meridi	an: S	STATE: UTAH
11. CHECI	K APPROPRIATE BOXES TO INDICATI	E NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
✓ DRILLING REPORT			
Report Date: 5/3/2013	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
0,0,00	WILDCAT WELL DETERMINATION	OTHER	OTHER:
Started	COMPLETED OPERATIONS. Clearly show all COmpleting the Well. Well TD	at 10,065.	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY May 09, 2013
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBE 720 929-6304	R TITLE Regulartory Analyst	
SIGNATURE N/A		DATE 5/3/2013	

Sundry Number: 38023 API Well Number: 43047525510000

	STATE OF UTAH			FORM 9
ι	DEPARTMENT OF NATURAL RESOUF DIVISION OF OIL, GAS, AND M			5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 010950-A
SUNDR	Y NOTICES AND REPORTS	ON WELI	_S	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In
	posals to drill new wells, significantl reenter plugged wells, or to drill horiz n for such proposals.			7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well				8. WELL NAME and NUMBER: NBU 921-22K4CS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.			9. API NUMBER: 43047525510000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	n Street, Suite 600, Denver, CO, 802	PHONE NUM 17 3779		9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1753 FSL 1640 FWL				COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NESW Section: 2	HIP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Me	ridian: S		STATE: UTAH
11. CHECI	K APPROPRIATE BOXES TO INDICA	ATE NATURE	OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TY	PE OF ACTION	
	ACIDIZE	ALTER CASI	NG	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TU	BING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE	E PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE	TREAT	NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND A	ABANDON	PLUG BACK
SPUD REPORT	✓ PRODUCTION START OR RESUME	RECLAMATI	ON OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK	TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FL	ARE	WATER DISPOSAL
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATU	JS EXTENSION	APD EXTENSION
5/16/2013	WILDCAT WELL DETERMINATION	OTHER		OTHER:
THE SUBJECT WELL	COMPLETED OPERATIONS. Clearly show WAS PLACED ON PRODUC WELL HISTORY WILL BE SUE COMPLETION REPORT	CTION ON BMITTED W	05/16/2013. THE	
NAME (PLEASE PRINT) Teena Paulo	PHONE NUM 720 929-6236		Regulatory Specialist	
SIGNATURE N/A		DATE 5/17/	/2013	

RECEIVED: May. 17, 2013

API Well Number: 43047525510000

Form 3160-4 FORM APPROVED UNITED STATES OMB No. 1004-0137 (August 2007) DEPARTMENT OF THE INTERIOR Expires: July 31, 2010 BUREAU OF LAND MANAGEMENT WELL COMPLETION OR RECOMPLETION REPORT AND LOG Lease Serial No. UTU010950A 1a. Type of Well Oil Well **⊠** Gas Well 6. If Indian, Allottee or Tribe Name □ Dry ☐ Other b. Type of Completion New Well ■ Work Over Deepen □ Plug Back □ Diff. Resvr. Unit or CA Agreement Name and No. Other UTU63047A 2. Name of Operator Contact: TEENA PAUL KERR MCGEE OIL&GAS ONSHOREE-Mail: teena.paulo@anadarko.com Contact: TEENA PAULO Lease Name and Well No. NBU 921-22K4CS PO BOX 173779 3a. Phone No. (include area code) 9. API Well No. DENVER, CO 80217 Ph: 720-929-6236 43-047-52551 10. Field and Pool, or Exploratory 4. Location of Well (Report location clearly and in accordance with Federal requirements)* NATURAL BUTTES NESW 1753FSL 1640FWL 40.019132 N Lat, 109.541467 W Lon At surface 11. Sec., T., R., M., or Block and Survey or Area Sec 22 T9S R21E Mer SLB At top prod interval reported below NESW 1587FSL 2141FWL 12. County or Parish State UINTÁH NESW 1568FSL 2142FWL UT 14. Date Spudded 11/28/2012 15. Date T.D. Reached 16. Date Completed 17. Elevations (DF, KB, RT, GL)* D & A Ready to Prod. 05/16/2013 02/22/2013 □ D & A 4911 KB 18. Total Depth: MD 10065 19. Plug Back T.D.: MD 10005 20. Depth Bridge Plug Set: MD TVD 10018 TVD 9958 TVD Type Electric & Other Mechanical Logs Run (Submit copy of each) CBL/GR/CCL/TEMP Was well cored? 22. **⊠** No Yes (Submit analysis) Was DST run? ▼ No Yes (Submit analysis) Yes (Submit analysis) Directional Survey? \square No 23. Casing and Liner Record (Report all strings set in well) No. of Sks. & Bottom Stage Cementer Slurry Vol. Hole Size Size/Grade Wt. (#/ft.) Cement Top* Amount Pulled (MD) (MD) Depth Type of Cement (BBL) 20.000 14.000 STL 28 36.7 11.000 8.625 IJ-55 28.0 24 2904 650 7.875 28 4911 1715 1480 4.500 I-80 11.6 7.875 4.500 P-110 11.6 4911 10052 24. Tubing Record Size Depth Set (MD) Packer Depth (MD) Size Depth Set (MD) Packer Depth (MD) Size Depth Set (MD) Packer Depth (MD) 9424 25. Producing Intervals 26. Perforation Record Formation Top Bottom Perforated Interval Size No. Holes Perf. Status A) 6808 0.360 78 **OPEN** WASATCH 7758 6808 TO 7758 B) **MESAVERDE** 7986 9884 7986 TO 9884 0.360 183 **OPEN** C) D)

27. Acid, Fracture, Treatment, Cement Squeeze, Etc Depth Interval Amount and Type of Material PUMP 14,219 BBLS SLICK H2O & 331,174 LBS 30/50 OTTAWA SAND

28. Production - Interval A Oil Gravity Produced Date Production BBL MCF BBL Corr. API Gravity Tested 05/16/2013 05/22/2013 0.0 2289.0 FLOWS FROM WELL 24 0.0 Choke Tbg. Press Csg. 24 Hr. Oil Water Gas:Oil Well Status MCF BBL Rate BBL Ratio Size Flwg. Press 20/64 SI 1465.0 0 2289 0 **PGW** 28a. Production - Interval B Water Gas Date First Test Oil Gas Oil Gravity Production Method Hours MCF BBL BBL Corr. API Produced Date Tested Production Gravity Choke 24 Hr. Water Gas:Oil Well Status Tbg. Press Csg. Oil Gas Size BBL Ratio Flwg. Press Rate

(See Instructions and spaces for additional data on reverse side)

28b. Produ	action - Interv	val C										
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravi	ty	Production Method		
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well	Status	1		
28c. Produ	iction - Interv	al D										
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravi	ty	Production Method		
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well	Status	•		
29. Dispos		Sold, usea	l for fuel, vent	ed, etc.)		·		<u> </u>				
Show tests, i	all important	zones of r	nclude Aquife porosity and c tested, cushid	ontents the	reof: Corec ne tool ope	l intervals an n, flowing ar	d all drill-stem ad shut-in pressures		31. For	mation (Log) Ma	arkers	
	Formation		Top	Bottom	ı	Descript	ions, Contents, etc.			Name		Top Meas. Deptl
32. Additi	onal remarks	(include ;	olugging proc	edure):					BIF MA WA	REEN RIVER RD'S NEST AHOGANY ASATCH ESAVERDE		1581 1840 2379 4974 7901
of the ft; LTC history tool in 33. Circle	surface hole C P-110 csg y, perforation the well, bu	e was dril was run n report a it no DV t	lled with an ' from 4932 ft	11 inch bit. . to 10,052 /ey. A Sui	DQX cso ft. Attac	y was run fro hed is the c	ne remainder om surface to 4932 hronological well oved to run a DV		DST Re	port	4. Directio	onal Survey
		_	g and cement	•	n	6. Core A	•		Other:	port	T. Difectio	nai Sui vey
	by certify that (please print)		Electr	ronic Subn	nission #21	10142 Verifi	orrect as determined ed by the BLM Wel ONSHORE,LP, se	l Inform ent to the	nation Sy e Vernal			ons):

Signature (Electronic Submission) Date 06/10/2013

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fradulent statements or representations as to any matter within its jurisdiction.

				U	S ROCI	KIES RI	EGION	
			(Opera	tion S	umma	ry Report	
Well: NBU 921-22	2K4CS (BLUE)						Spud Date: 12/2	28/2012
Project: UTAH-UI			Site: NBU	921-22K	(PAD		·	Rig Name No: PROPETRO 12/12, H&P 318/318
Event: DRILLING	i		Start Date	. 12/2/20	112			End Date: 2/24/2013
	KB @4,911.00usft (ab	ove Mean Se	<u>'</u>			L /S/21/E/22	2/0/0/26/PM/S/17	
Level)	15 @ 1,011.00doit (da	ovo modii oo	٠ ا					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
12/20/2012	0:00 - 0:00	24.00	MIRU	01	В	Р	(3.3.4)	SHUT DOWN FOR THE CHRISTMAS HOLLIDAYS.
12/21/2012	0:00 - 0:00	24.00	MIRU	01	В	Р		SHUT DOWN FOR THE CHRISTMAS HOLLIDAYS.
12/22/2012	0:00 - 0:00	24.00	MIRU	01	В	Р		SHUT DOWN FOR THE CHRISTMAS HOLLIDAYS.
12/23/2012	0:00 - 0:00	24.00	MIRU	01	В	Р		SHUT DOWN FOR THE CHRISTMAS HOLLIDAYS.
12/24/2012	0:00 - 0:00	24.00	MIRU	01	В	Р		SHUT DOWN FOR THE CHRISTMAS HOLLIDAYS.
12/25/2012	0:00 - 0:00	24.00	MIRU	01	В	Р		SHUT DOWN FOR THE CHRISTMAS HOLLIDAYS.
12/26/2012	0:00 - 0:00	24.00	MIRU	01	В	Р		SHUT DOWN FOR THE CHRISTMAS HOLLIDAYS.
12/27/2012	0:00 - 0:00	24.00	MIRU	01	В	Р		SHUT DOWN FOR THE CHRISTMAS HOLLIDAYS.
12/28/2012	0:00 - 16:00	16.00	MIRU	01	В	Р		SHUT DOWN FOR THE CHRISTMAS HOLLIDAYS.
	16:00 - 20:30	4.50	MIRU	01	В	Р		RIG UP SET MATTING BOARD, SET RIG IN PLACE, CATWALK, PIPE RACKS, PLACE BOTTOME HOLE ASSEMBLY
	20:30 - 21:00	0.50	MIRU	01	С	P		PRE SPUD JOB SAFETY MEETING REVEW DIRECTIONAL PLANS AND PLATS AND VERIFY LAT/LONGS AND WELL ORDER VERIFY DIRECTIONAL DRILLERS PLAN IS THE MOST RECENT AND APPROVED VERSION REFERENCE WELLBORE DIAGRAMS FOR EXACT CASING DESIGN AND GENERAL OVERVEW OF WELLBORE, PRIOR TO SPUD. FINISH PICKING UP BHA. PICK UP NOV 1.83 DEGREE BENT MOTOR (RUN # 1)17 REV/GAL SN (104694-6). PICK UP 12.25 Q506 DRILL BIT RUN 30 SN (7137066)
	21:00 - 22:30	1.50	DRLSUR	02	В	P		SPUD @ 12/28/2012 21:00. DRILL 12.25" HOLE 4'-210' (206', 110'/PER HOUR). 12.25" BIT ON 30th RUN. WEIGHT ON BIT 5-15 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF (BOTTOM) 800/600. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROTATE 20/20/20 K. DRAG 0 K. CIRCULATE CLOSED LOOP SYSTEM WITH 8.3# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. DRILL DOWN TO 210' WITH 6" DRILL COLLARS.
	22:30 - 0:00	1.50	DRLSUR	06	A	Р		PRE JOB SAFETY MEETING, CIRC 15 MINUTES AND, TRIP OUT TO CHANGE ASSEMBLY. LAY DOWN 6" DRILL COLLARS, BREAK 12 1/4" BIT. MAKE UP Q506F 11" BIT (2ND RUN) (SN 7141916) PICK UP 8" DIRECTIONAL ASSEMBLY. INSTALL EM TOOL, TRIP IN HOLE.

API Well Number: 43047525510000 US ROCKIES REGION **Operation Summary Report** Spud Date: 12/28/2012 Well: NBU 921-22K4CS (BLUE) Project: UTAH-UINTAH Site: NBU 921-22K PAD Rig Name No: PROPETRO 12/12, H&P 318/318 **Event: DRILLING** End Date: 2/24/2013 Start Date: 12/2/2012 UWI: NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0 Active Datum: RKB @4,911.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 12/29/2012 0:00 - 0:30 0.50 DRLSUR 06 Ρ Α PRE JOB SAFETY MEETING. CIRCULATE 15 MINUTES AND, TRIP OUT TO CHANGE ASSEMBLY. DOWN 6" DRILL COLLARS, BREAK 12 1/4" BIT. MAKE UP Q506F 11" BIT (1ST RUN) (SN 7029640) PICK UP 8" DIRECTIONAL ASSEMBLY. EM TOOL, TRIP IN HOLE. 0:30 - 6:00 5.50 **DRLSUR** 02 В DRILL 11". SURFACE HOLE 210'-800', (590', 107'/PER HOUR). WEIGHT ON BIT 15-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE PRESSURE ON/OFF(BOTTOM) 491. 1000/830 ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 60/45/50 K. DRAG 10 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES **CURRENTLY 1.62'** SOUTH 1.05' WEST OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. NO HOLE ISSUES. 6:00 - 12:00 DRILL 11". SURFACE HOLE 800'-1400', (600', 6.00 **DRLSUR** 100'/PER HOUR). WEIGHT ON BIT 15-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE PRESSURE ON/OFF(BOTTOM) 491 1200/1000 ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 60/50/55 K. DRAG 5 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES CURRENTLY 1.0' NORTH 1.0' WEST OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. NO HOLE ISSUES.

				Opera	tion S	umma	ry Report	
Vell: NBU 921-2	22K4CS (BLUE)						Spud Date: 12	//28/2012
Project: UTAH-L	. ,		Site: NBL	J 921-22k	(PAD		•	Rig Name No: PROPETRO 12/12, H&P 318/318
event: DRILLIN	G		Start Date	e: 12/2/20)12			End Date: 2/24/2013
Active Datum: R	KB @4,911.00usft (al	oove Mean S	ea	UWI: NI	E/SW/0/9	/S/21/E/22	/0/0/26/PM/S/17	753/W/0/1640/0/0
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	12:00 - 18:00	6.00	DRLSUR	02	В	P		DRILL 11". SURFACE HOLE 1400'-2030', (630', 105'/PER HOUR). WEIGHT ON BIT 15-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 1400/1100. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 70/60/65 K. DRAG 5 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES CURRENTLY 3.0' NORTH .23' WEST OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS.
	18:00 - 0:00	6.00	DRLSUR	02	В	Р		DRILL 11". SURFACE HOLE 2030'-2480', (450', 75'/PER HOUR). WEIGHT ON BIT 15-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE 491. PRESSURE ON/OFF(BOTTOM) 1600/1450. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 80/70/75 K. DRAG 5 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES CURRENTLY 12' NORTH 3.2' EAST OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# WATER. RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS.

API Well Number: 43047525510000 US ROCKIES REGION **Operation Summary Report** Well: NBU 921-22K4CS (BLUE) Spud Date: 12/28/2012 Project: UTAH-UINTAH Site: NBU 921-22K PAD Rig Name No: PROPETRO 12/12, H&P 318/318 **Event: DRILLING** End Date: 2/24/2013 Start Date: 12/2/2012 UWI: NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0 Active Datum: RKB @4,911.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 12/30/2012 0:00 - 5:30 5.50 DRLSUR 02 В Ρ DRILL 11". SURFACE HOLE 2480'-2914', (434', 78'/PER HOUR). TD@12/30/2012 05:30 WEIGHT ON BIT 15-25 K. STROKES PER MINUTE 120 GALLONS PER MINUTE PRESSURE ON/OFF(BOTTOM) 1850/1650. ROTARY RPM 55, MOTOR RPM 83, TOTAL RPM 138. UP/DOWN/ ROT 85/75/80 K. DRAG 5 K. SLIDING 15' PER 90'OF ROTATION GETTING 1.5 DEGREE BUILD RATES **CURRENTLY 7.4' NORTH** 2.4' EAST OF THE LINE CIRCULATE CLOSED LOOP SYSTEM WITH 8.4# RUNNING VOLUME THROUGH 1 CENTRAFUGE DEWATERING AND, RUNNING VOLUME OVER BOTH SHAKERS. NO HOLE ISSUES. 5:30 - 7:30 2 00 DRLSUR 05 Р CIRCULATE AND CONDITION HOLE, VOLUME IS CLEAN COMING OVER SHAKERS, 4-400 BBL UPRIGHT'S FULL AND 2-400 BBL UPRIGHTS EMPTY, MUD TANKS FULL. 7:30 - 11:30 4.00 **CSGSUR** 06 TRIP OUT OF HOLF LAY DOWN DRILL STRING, BOTTOM HOLE ASSEMBLY, DIRECTIONAL TOOLS, MOTOR AND, CLEAR TOOL AREA. 11:30 - 12:30 1 00 **CSGSUR** Р 06 Α PRE JOB SAFETY MEETING, MOVE PIPE RACKS AND CATWALK. PULL DIVERTER HEAD. RIG UP TO RUN SURFACE CASING CLEAR UNRELATED TOOLS. 12:30 - 16:30 4 00 **CSGSUR** 12 C Р RUN 65 JOINTS OF 8-5/8". 28# J-55 LTC CASING. RAN 1 CENTRALIZER ON FIRST THREE JOINTS, AND EVERY OTHER JOINT FOR 2 JOINTS FOR A TOTAL OF 5 CENTRALIZERS. RUN A TOTAL OF 65 JOINTS. RUN CASING TO BOTTOM CIRCULATE AND PUMP LAST TWO JOINTS DOWN. SET FLOAT SHOE @ 2883.63' KB. SET TOP OF BAFFLE PLATE @ 2837.48' KB.

API Well Number: 43047525510000 US ROCKIES REGION **Operation Summary Report** Well: NBU 921-22K4CS (BLUE) Spud Date: 12/28/2012 Project: UTAH-UINTAH Site: NBU 921-22K PAD Rig Name No: PROPETRO 12/12, H&P 318/318 **Event: DRILLING** End Date: 2/24/2013 Start Date: 12/2/2012 UWI: NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0 Active Datum: RKB @4,911.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 16:30 - 20:00 3.50 **CSGSUR** 12 Ρ Ε PRE JOB SAFETY MEETING. RELEASE RIG @ 12/30/2012 20:00 RAN 200 ft OF 1 lin. PIPE DOWN BACK-SIDE OF CASING. PRESSURE TEST LINES TO 2000 PSI. PUMP 170 BBLS OF WATER AHEAD CLEARING THE SHOE. MIX AND PUMP 20 BBLS OF 8.5# GEL WATER AHEAD. MIX AND PUMP (300 sx) 152.8 BBLS OF 12.0# 2.86 YIELD LEAD CEMENT. MIX AND PUMP (170 sx) 34.8 BBLS OF 15.8# 1.15 YIELD TAIL CEMENT. DROP PLUG ON FLY, DISPLACE WITH 173 BBLS OF H2O, FULL RETURNS THROUGH OUT JOB, FINAL LIFT OF 700 PSI AT 3 BBL/MINUTE. BUMP THE PLUGG WITH 1000 PSI, HELD 1000 PSI FOR 5 MINUTES, TESTED FLOAT AND FLOAT HELD. SHUT DOWN AND WASH UP. 20:00 - 20:00 0.00 **CSGSUR** 12 F PUMP CEMENT DOWN ONE INCH PIPE WITH 150 sx (30.7 bbls.)SAME TAIL CEMENT 3 BBL RETURNS TO SURFACE, CEMENT HELD AT SURFACE. SHUT DOWN AND WASH UP. RIG DOWN CEMENTERS. (CEMENT JOB FINISHED @ 12/30/2012 21:30) 2/18/2013 14:00 - 15:00 1.00 MIRU3 SKID RIG, RIG UP ROTARY TOOLS, 15:00 - 17:00 2.00 **PRPSPD** NIPPLE UP BOP & EQUIPMENT 14 Α 17:00 - 0:00 7.00 **PRPSPD** Ρ 15 Α SAFETY MEETING W/ A-1 TESTER, TEST CHOKE, TIW DART VALVE, UPPER KELLY VALVE, LOWER KELLY VALVE, PIPE RAMS, BLIND RAMS, HCR VALVE, OUTSIDE CKOKE VALVE, INSIDE& OUTSIDE MANIFOLD VALVES, & SUPER CHOKE @ 250psi LOW FOR 5 MINUTES, AND @ 5000psi HIGH FOR 10 MINUTES.TEST ANNULAR @ 250psi LOW FOR 5 MINUTES AND @ 2500psi HIGH FOR 10 MINUTES, TEST SWACO MANIFOLD TO 1000 PSI F/ 10 MIN 2/19/2013 0:00 PRPSPD Р - 2:00 2.00 15 FINISH TESTING SWACO MANIFOLD, 1000 PSI F/ 10 MIN, TEST CASING TO 1500 PSI F/30 MIN, RIG DOWN TESTER 2:00 - 2:30 0.50 **PRPSPD** 14 В Ρ INSTALL WEAR BUSHING 2:30 - 7:00 4 50 PRPSPD Р 06 Α PICKUP SECURITY MM65M BIT, SDI .23 RPG/ 1.5 BEND MOTOR, MWD , ORIENT MWD, TRIP IN HOLE , TAG CEMENT @ 2743' 7:00 - 8:30 Ρ 1.50 DRLPRV 02 F DRILL, CEMENT, FLOAT EQUIPMENT & OPEN HOLE F/ 2743' TP 2934'

API Well Number: 43047525510000 **US ROCKIES REGION Operation Summary Report** Well: NBU 921-22K4CS (BLUE) Spud Date: 12/28/2012 Project: UTAH-UINTAH Site: NBU 921-22K PAD Rig Name No: PROPETRO 12/12, H&P 318/318 **Event: DRILLING** End Date: 2/24/2013 Start Date: 12/2/2012 UWI: NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0 Active Datum: RKB @4,911.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 8:30 - 16:00 7.50 **DRLPRV** 02 Ρ В DRILL (ROTATE/SLIDE) F/ 2934' TO 3769' RATE OF PENATRATION= 835, @ 111.3 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 57 ~ TOTAL= 181 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2000/1527 TORQUE~ ON/OFF = 7000/2000 PICKUP/SLACK OFF/ROTATE= 120/98/105 MUD WEIGHT= 8.8+ / VISCOSITY= 28 **NOV DEWATERING** SWACO OFF LINE SLIDE 101' IN 1.51 HRS = 66.8' HR BIT POSITION= 1.5' NORTH & 2.8' WEST OF TARGET NO LOSSES 16:00 - 16:30 0.50 **DRLPRV** Ρ **RIG SERVICE** 07 16:30 - 0:00 Р 7.50 DRLPRV В 02 DRILL (ROTATE/SLIDE) F/ 3769' TO 4865' ROTATE OF PENATRATION= 1096' @ 146.1 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 57 ~ TOTAL= 181 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2100/1585 TORQUE~ ON/OFF = 8000/4000 PICKUP/SLACK OFF/ROTATE= 138/112/124 MUD WEIGHT= 8.9 / VISCOSITY= 32 **NOV DEWATERING** SWACO OFF LINE SLIDE 35' IN .92 HRS = 38' HR BIT POSITION= NORTH & 'WEST OF TARGET LINE LOST 50 BBLS TO SEEPAGE 2/20/2013 0:00 - 6:00 6.00 **DRLPRV** 02 В Р DRILL (ROTATE/SLIDE) F/ 4865' TO 5560' ROTATE OF PENATRATION= 695' @115.8 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 57 ~ TOTAL= 181 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2100/1585 TORQUE~ ON/OFF = 8000/4000 PICKUP/SLACK OFF/ROTATE= 154/117/131 MUD WEIGHT= 8.9 / VISCOSITY= 30 **NOV DEWATERING** SWACO OFF LINE SLIDE 30' IN .66 HRS = 45.4' HR BIT POSITION= 9.3 NORTH & 9.2 ' WEST OF TARGET LOST 50 BBLS TO SEEPAGE 5' TO 15' CONNECTION FLARE

API Well Number: 43047525510000 **US ROCKIES REGION Operation Summary Report** Well: NBU 921-22K4CS (BLUE) Spud Date: 12/28/2012 Project: UTAH-UINTAH Site: NBU 921-22K PAD Rig Name No: PROPETRO 12/12, H&P 318/318 **Event: DRILLING** End Date: 2/24/2013 Start Date: 12/2/2012 UWI: NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0 Active Datum: RKB @4,911.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 6:00 - 15:30 9.50 **DRLPRV** 02 Ρ В DRILL(ROTATE/SLIDE) F/5560' TO 6695' ROTATE OF PENATRATION= '1135'@ 119.7 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 55 ~ TOTAL= 179 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2100/1700 TORQUE~ ON/OFF = 9000/6000 PICKUP/SLACK OFF/ROTATE= 175/130/150 MUD WEIGHT= 8.9 / VISCOSITY= 32 **NOV DEWATERING** SWACO OFF LINE SLIDE 26' IN .75 HRS = 34.6' HR BIT POSITION= 15.5 NORTH & 0 'WEST OF TARGET LINE LOST 50 BBLS TO SEEPAGE 5' TO 15' CONNECTION FLARE 15:30 - 16:00 0.50 DRLPRV RIG SERVICE 16:00 - 0:00 02 8.00 **DRLPRV** В DRILL(ROTATE/SLIDE) F/6695'TO 7280' ROTATE OF PENATRATION= 585 '@ 73.1 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 60 ~ TOTAL= 184 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2200 / 1700 TORQUE~ ON/OFF = 8000 / 7000 PICKUP/SLACK OFF/ROTATE= 190/135/155 MUD WEIGHT= 8.9 / VISCOSITY= 33 **NOV DEWATERING** SWACO OFF LINE SLIDE 24' IN 1.42 HRS = 16.9' HR BIT POSITION= 8.5' NORTH & 9.5 ' WEST OF TARGET LINE LOST 45 BBLS TO SEEPAGE 5' TO 15' CONNECTION FLARE 2/21/2013 0:00 - 6:00 6.00 **DRLPRV** 02 В DRILL(ROTATE/SLIDE) F/7280' TO 7636' ROTATE OF PENATRATION= 356 '@ 59.3 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 60 ~ TOTAL= 184 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2200 / 1700 TORQUE~ ON/OFF = 9000 / 7000 PICKUP/SLACK OFF/ROTATE= 203/140/168 MUD WEIGHT= 8.9 / VISCOSITY= 33 **NOV DEWATERING** SWACO OFF LINE SLIDE 12' IN .75 HRS = 16' HR BIT POSITION= 10.1 ' NORTH & 10.6 ' WEST OF TARGET LINE LOST 30 BBLS TO SEEPAGE 5' TO 15' CONNECTION FLARE

API Well Number: 43047525510000 **US ROCKIES REGION Operation Summary Report** Well: NBU 921-22K4CS (BLUE) Spud Date: 12/28/2012 Project: UTAH-UINTAH Site: NBU 921-22K PAD Rig Name No: PROPETRO 12/12, H&P 318/318 **Event: DRILLING** End Date: 2/24/2013 Start Date: 12/2/2012 UWI: NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0 Active Datum: RKB @4,911.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 6:00 - 15:30 9.50 **DRLPRV** 02 Ρ В DRILL(ROTATE/SLIDE) F/7636' TO 8200' ROTATE OF PENATRATION= 564 '@59.3 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 60 ~ TOTAL= 184 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2100 / 1750 TORQUE~ ON/OFF = 9000 / 7000 PICKUP/SLACK OFF/ROTATE= 215/145/175 MUD WEIGHT= 9.0 / VISCOSITY= 34 **NOV DEWATERING** SWACO OFF LINE SLIDE HRS = 20' IN .75 HRS = 26.6' HR BIT POSITION= 14.2 ' NORTH & 12.4 ' WEST OF TARGET LINE LOST 30 BBLS TO SEEPAGE 5' TO 10' CONNECTION FLARE 15:30 - 16:00 0.50 DRLPRV RIG SERVICE 16:00 - 0:00 В Р 8.00 DRLPRV 02 DRILL(ROTATE/SLIDE) F/8200' TO 8800' ROTATE OF PENATRATION= 600 '@ 75 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 60 ~ TOTAL= 184 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2450/2050 TORQUE~ ON/OFF = 10/9 PICKUP/SLACK OFF/ROTATE= 235/153/183 MUD WEIGHT= 9.0 / VISCOSITY= 35 **NOV DEWATERING** SWACO OFF LINE SLIDE HRS = 12' IN .58 HRS = 20.6' HR BIT POSITION= 11.5 ' NORTH & 12.9 ' WEST OF TARGET LINE LOST 25 BBLS TO SEEPAGE 5' TO 10' CONNECTION FLARE 2/22/2013 0:00 - 6:00 6.00 **DRLPRV** 02 DRILL(ROTATE/SLIDE) F/ 8800' TO 9144' ROTATE OF PENATRATION= 344' '@ 57.3 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 60 ~ TOTAL= 184 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2450/2050 TORQUE~ ON/OFF = 10/10 PICKUP/SLACK OFF/ROTATE= 240/155/185 MUD WEIGHT= 9.2 / VISCOSITY= 36 **NOV DEWATERING** SWACO OFF LINE SLIDE HRS 12' IN .75 HRS = 16' HR BIT POSITION= 8.1' NORTH & 11.2 ' WEST OF TARGET LINE LOST 40 BBLS TO SEEPAGE 5' TO 10' BACK GROUND FLARE 10' TO 20' CONNECTION FLARE

API Well Number: 43047525510000 US ROCKIES REGION **Operation Summary Report** Well: NBU 921-22K4CS (BLUE) Spud Date: 12/28/2012 Project: UTAH-UINTAH Site: NBU 921-22K PAD Rig Name No: PROPETRO 12/12, H&P 318/318 **Event: DRILLING** End Date: 2/24/2013 Start Date: 12/2/2012 UWI: NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0 Active Datum: RKB @4,911.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 6:00 - 16:30 10.50 **DRLPRV** 02 Ρ В DRILL(ROTATE/SLIDE) F/9144' TO 9711' ROTATE OF PENATRATION= 567 '@ 54 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 60 ~ TOTAL= 184 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2500/2000 TORQUE~ ON/OFF = 14000/10000 PICKUP/SLACK OFF/ROTATE=255/160/190 MUD WEIGHT= 9.2 / VISCOSITY= 36 **NOV DEWATERING** SWACO OFF LINE SLIDE HRS = 0 BIT POSITION= 1.6 ' NORTH & 7.5 ' WEST OF TARGET LINE LOST 75 BBLS TO SEEPAGE 5' TO 10' BACK GROUND FLARE 15' TO 25' CONNECTION FLARE 16:30 - 17:00 0.50 **DRLPRV** 07 **RIG SERVICE** 17:00 - 23:30 6.50 **DRLPRV** 02 В Р DRILL(ROTATE/SLIDE) F/ 9711' TO 10065' TD @ 23:30 2/22/2013 ROTATE OF PENATRATION= 354 '@ 54.4 FPH WEIGHT ON BIT = 24-28K RPM ~ MUD MOTOR =124 TOP DRIVE= 60 ~ TOTAL= 184 GALLONS PER MINUTE = 540 STROKES PER MINUTE = 120 STAND PIPE PSI~0N/OFF = 2500/2200 TORQUE~ ON/OFF = 13000/10000 PICKUP/SLACK OFF/ROTATE= 260/165/206 MUD WEIGHT= 9.3 / VISCOSITY= 37 **NOV DEWATERING** SWACO OFF LINE SLIDE HRS = 0 BIT POSITION= 6 'SOUTH & 2.5 'WEST OF TARGET LINE LOST 25 BBLS TO SEEPAGE 5' TO 10' BACK GROUND FLARE 15' TO 25' CONNECTION FLARE *** TROUBLE SHOOT MWD*** F/ LAST SURVEY 23:30 - 0:00 0.50 **DRLPRV** 7 22 L 0:00 2/23/2013 - 4:30 4.50 **DRLPRV** 05 С CIRCULATE & CONDITION, DISPLACE HOLE W/ HEAVY MUD, 11.5#, VIS 40, LCM 5% 4:30 - 6:00 Р 1.50 **DRLPRV** 06 Ε WIPER TRIP 10 STANDS, NO PROBLEMS 6:00 - 7:30 DRLPRV С Р CIRCULATE & CONDITION, NO FLARE 1.50 7:30 - 13:30 6.00 DRLPRV 06 Α Р TRIP OUT OF HOLE LAY DOWN MWD, MOTOR & BIT 13:30 - 14:00 0.50 DRLPRV Р 14 В PULL WEAR BUSHING 14:00 - 14:30 0.50 **CSGPRO** 12 Ρ **RIG UP CASERS** Α 14:30 - 23:00 8.50 **CSGPRO** 12 С Р SAFETY MEETING W/ KIMZEY CASERS, RUN 228 JTS 4.5", 11.6# (116 JTS LT&C / 112 JTS DQX) SHOE 10052', TOP OF FLOAT 10005', TOP OF M.V MARKER 7834', TOP OF X/O 4911', TEST FLOAT EQUIP & FILL PIPE EVERY 1500', TAG FILL @ 10027' , WASH DOWN F/ 10027' TO 10052', LAND CASING @ 102,000

API Well Number: 43047525510000 US ROCKIES REGION **Operation Summary Report** Spud Date: 12/28/2012 Well: NBU 921-22K4CS (BLUE) Project: UTAH-UINTAH Site: NBU 921-22K PAD Rig Name No: PROPETRO 12/12, H&P 318/318 **Event: DRILLING** End Date: 2/24/2013 Start Date: 12/2/2012 UWI: NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0 Active Datum: RKB @4,911.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 23:00 - 0:00 1.00 **CSGPRO** 05 D Ρ CIRCULATE F/ CEMENT, RIG DOWN CASERS 0:00 - 4:00 Р 2/24/2013 4.00 Ε **CSGPRO** 12 SAFETY MEETING W/ BJ SERVICES, RIG UP TO CASING, CEMENT PROD CASING, PRESSURE TEST TO 5000 PSI, PUMP 25 BBLS SPACER, 560 SX, 197.5 BBLS, PREMIUM LITE II CEMENT + .05 LBS/SX STATIC FREE+ 0.4% BWOC FL-52 + 0.2% BWOC SODIUM METASILICATE + 6% BWOC BENTONITE II + 0.4% BWOC R-3 +0.25 LBS/SACK CELLO FLAKE +5 LBS/SX KOL-SEAL,50 LB BAG 84.8 % FRESH WATER ,12.5# 1.98 YLD, LEAD , 1155 SACKS , 273.6 BBLS, (50:50) POZ (FLY ASH): CLASS G CEMENT + 0.005 LBS/SACK STATIC FREE + 10% BWOW SODIUM CHLORIDE + 0.9% BWOC R-3 +.5% BWOC EC-1+ 0.002 GPS FP-6L +1.2% BWOC SODIUM METASILICATE + 2% BWOC BENTONITE II + 59.1% FRESH WATER 14.3# ,1.33 YLD TAIL, SHUT DOWN WASH UP ,DROP TOP PLUG, DISPLACE W/ 155.8 BBLS CLAY CARE + 1 GAL MAGNACIDE @ $8.34~\mathrm{PPG},~\mathrm{FINAL~LIFT~2764~PSI}\;,~\mathrm{BUMP~PLUG~@~500}$ OVER, PLUG DOWN @ 02:51 2/24/2013, FLOATS HELD F/ 5 MIN , FULL RETURNS , 10 BBL'S SPACER BACK TO SURFACE, NO CEMENT ,TOP OF TAIL EST 4447', FLUSH STACK AND LINES, RIG DOWN **CEMENTERS** - 5:00 Р 1.00 **CSGPRO** В 14 SET PACK OFF ASSEMBALY, LAY DOWN LANDING **JOINT** 5:00 - 6:00 1.00 **CSGPRO** 14 Α Ρ NIPPLE DOWN BOP & EQUIP 6:00 - 7:00 1.00 MIRU3 Ρ 01 Ε RIG DOWN ROTARY TOOLS, PREPARE RIG F/SKID

General

Customer Information 1:

Company	US ROCKIES REGION
Representative	
Address	

Well/Wellbore Information 1.2

				P
				API
			US ROCKIES REGION	REGION M
				11
General				Num
Customer Information				ıber
				:
Company	US ROCKIES REGION			4
Representative				30
Address)4'
Well/Wellbore Information	tion			7525
Well	NBU 921-22K4CS (BLUE)	Wellbore No.	Ю	510
Well Name	NBU 921-22K4CS	Wellbore Name	NBU 921-22K4CS	00
Report No.	_	Report Date	5/6/2013	00
Project	LTAH-UINTAH	Site	NBU 921-22K PAD)
Rig Name/No.		Event	COMPLETION	
Start Date	4/30/2013	End Date	5/16/2013	
Spud Date	12/28/2012	Active Datum	RKB @4,911.00usft (above Mean Sea Level)	
UWI	NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0			

General ..

Contractor	Job Method	Supervisor	
Perforated Assembly	Conveyed Method		

Summary

1.5

Initial Conditions 1.4

Fluid Type		Fluid Density	Gross Interval	6,808.0 (usft)-9,884.0 (usft Start Date/Time	Start Date/Time	5/6/2013 12:00AM
Surface Press		Estimate Res Press	No. of Intervals	69	69 End Date/Time	5/6/2013 12:00AM
TVD Fluid Top		Fluid Head	Total Shots	261	261 Net Perforation Interval	87.00 (usft)
Hydrostatic Press		Press Difference	Avg Shot Density	3.00 (shot/ft)	3.00 (shot/ft) Final Surface Pressure	
Balance Cond NEUTRAL	NEUTRAL				Final Press Date	

Intervals

Perforated Interval 2.1

May 29, 2013 at 12:02 pm

Misrur	
Reason	23.00 PRODUCTIO N
Charge Weight (gram)	23.00
Phasing Charge Desc /Charge (°) Manufacturer	
Phasing (°)	120.00
Carr Size (in)	3.375
Carr Type /Stage No	EXP/
Diamete r (in)	0.360 EXP/
Misfires/ Add. Shot	
Shot Density (shot/ft)	3.00
CCL@ CCL-T MDTop MD Base (usft) S (usft) (usft) (usft)	6.808.0 6.809.0
MD Top (usft)	6.808.0
CCL-T S (usft)	
(Jsn)	
Formation/ Reservoir	WASATCH/
Date	5/6/2013 12:00AM

OpenWells

Perforated Interval (Continued)

													US ROCKIES REGION		API Wel
2.1 Pe	Perforated Interval (Continued)	Continu	ed)											I NU	1 Nu
Date	Formation/ Reservoir	(Jysn) (nstt)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Misfires/ Density Add. Shot (shot/ft)	Diamete C r (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun	ımber
5/6/2013 12:00AM	WASATCH/			6,838.0	6,839.0	3.00	0.360 EXP/	/c	3.375	120.00		23.00	23.00 PRODUCTIO N	. 4	: 4
5/6/2013 12:00AM	WASATCH/			6,878.0	6,879.0	3.00	0.360 EXP/	<i>(</i> 0	3.375	120.00		23.00	23.00 PRODUCTIO N	1304	1304
5/6/2013 12:00AM	WASATCH/			6,907.0	6,908.0	3.00	0.360 EXP/	<i>(</i>	3.375	120.00		23.00	23.00 PRODUCTIO N	± / ɔ.	175°
5/6/2013 12:00AM	WASATCH/			7,012.0	7,013.0	3.00	0.360 EXP/	<i>\</i> 0	3.375	120.00		23.00	23.00 PRODUCTIO N	255	255
5/6/2013 12:00AM	WASATCH/			7,030.0	7,031.0	3.00	0.360 EXP/	,	3.375	120.00		23.00	23.00 PRODUCTIO N	100	100
5/6/2013 12:00AM	WASATCH/			7,056.0	7,057.0	3.00	0.360 EXP/	<i>\</i> 0	3.375	120.00		23.00	23.00 PRODUCTIO N	00	0.0
5/6/2013 12:00AM	WASATCH/			7,120.0	7,121.0	3.00	0.360 EXP/	/ 0	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,142.0	7,143.0	3.00	0.360 EXP/	<i>h</i>	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,194.0	7,195.0	3.00	0.360 EXP/)n	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,230.0	7,231.0	3.00	0.360 EXP/	<i>\</i> 0	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,254.0	7,255.0	3.00	0.360 EXP/	/0	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,277.0	7,278.0	3.00	0.360 EXP/	/0	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,295.0	7,296.0	3.00	0.360 EXP/	le	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,336.0	7,337.0	3.00	0.360 EXP/	/c	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,437.0	7,438.0	3.00	0.360 EXP/	/c	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,477.0	7,479.0	3.00	0.360 EXP/	<i>(</i> c	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,505.0	7,507.0	3.00	0.360 EXP/	/0	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,561.0	7,562.0	3.00	0.360 EXP/	/c	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,584.0	7,585.0	3.00	0.360 EXP/	/c	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,595.0	7,596.0	3.00	0.360 EXP/	la	3.375	120.00		23.00	23.00 PRODUCTIO N		
5/6/2013 12:00AM	WASATCH/			7,733.0	7,734.0	3.00	0.360 EXP/	/a	3.375	120.00		23.00	23.00 PRODUCTIO N		

Perforated Interval (Continued) 2.1

)	US ROCKIES REGION		API We
2.1 Pe	Perforated Interval (Continued)	onfinue	=												II NU	ll Nu
Date	Formation/ Reservoir	(JJSN)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Stage No	Carr Size (in)	Phasing Charg	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun	mber
5/6/2013 12:00AM	WASATCH/			7,756.0	7,758.0	3.00		<u>0</u>	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		: 4
5/6/2013 12:00AM	MESAVERDE/			7,986.0	7,987.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N	302	1304
5/6/2013 12:00AM	MESAVERDE/			8,024.0	8,026.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N	± / 5 /	1752
5/6/2013 12:00AM	MESAVERDE/			8,153.0	8,155.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N	<u> </u>	255
5/6/2013 12:00AM	MESAVERDE/			8,164.0	8,166.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N	100	100
5/6/2013 12:00AM	MESAVERDE/			8,257.0	8,258.0	3.00		0.360 EXP/	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N	00	0.0
5/6/2013 12:00AM	MESAVERDE/			8,308.0	8,309.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,331.0	8,332.0	3.00		0.360 EXP/	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,348.0	8,349.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,370.0	8,371.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,402.0	8,403.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,414.0	8,416.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,544.0	8,546.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,616.0	8,618.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,672.0	8,675.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,710.0	8,711.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,726.0	8,728.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,844.0	8,846.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,864.0	8,866.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,906.0	8,907.0	3.00		0.360 EXP/	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			8,924.0	8,925.0	3.00		0.360 EXP/	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		

May 29, 2013 at 12:02 pm

													-	US ROCKIES REGION		API We
2.1 Pe	Perforated Interval (Continued)	ontinue	ਰ												II NU	ll Nu
Date	Formation/ Reservoir	(JJSN)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Stage No	Carr Size (in)	Phasing Char	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun	mber
5/6/2013 12:00AM	MESAVERDE/			8,964.0	8,965.0	3.00		<u>0</u>	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		: 4
5/6/2013 12:00AM	MESAVERDE/			9,001.0	9,002.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N	302	1304
5/6/2013 12:00AM	MESAVERDE/			9,033.0	9,034.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N	± / 5 /	1752
5/6/2013 12:00AM	MESAVERDE/			0.990,6	0.690,6	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N	<u> </u>	255
5/6/2013 12:00AM	MESAVERDE/			9,199.0	9,200.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N	100	100
5/6/2013 12:00AM	MESAVERDE/			9,233.0	9,234.0	3.00		0.360 EXP/	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N	00	0.0
5/6/2013 12:00AM	MESAVERDE/			9,282.0	9,283.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,328.0	9,329.0	3.00		0.360 EXP/	XP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,354.0	9,355.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,374.0	9,375.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,389.0	9,390.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,412.0	9,413.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,454.0	9,455.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,491.0	9,492.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,534.0	9,535.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,557.0	9,558.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,574.0	9,575.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,592.0	9,593.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			0.909,6	9,608.0	3.00		0.360 E	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,653.0	9,654.0	3.00		0.360 EXP/	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		
5/6/2013 12:00AM	MESAVERDE/			9,670.0	9,671.0	3.00		0.360 EXP/	EXP/	3.375	120.00		23.00 F	23.00 PRODUCTIO N		

RECEIVED: Jun. 10, 2013

May 29, 2013 at 12:02 pm


OpenWells

Perforated Interval (Continued)

2.1 Perforated Interval (Continued) Date Reservoir Reservoir Reservoir Reservoir Reservoir Reservoir Reservoir Reservoir (usft)			US ROCKIES REGION	REGION
Formation/ Reservoir CCL-7 (usft) MD Top (usft) MD Base (usft) Shot (usft) Misfires/ (shot/ff) Diamete (in) Carr Type /Stage No (shot/ff) Carr (in) MESAVERDE/ (usft)				l Nu
MESAVERDE/ 9,690.0 9,691.0 3.00 0.360 EXP/ MESAVERDE/ 9,716.0 9,717.0 3.00 0.360 EXP/ MESAVERDE/ 9,772.0 9,773.0 3.00 0.360 EXP/ MESAVERDE/ 9,845.0 9,846.0 3.00 0.360 EXP/	Carr Type /Stage No Carr Size Size (in)	Phasing Charge Desc /Charge (°) Manufacturer	Charge Reason Weight (gram)	wber unsim
MESAVERDE/ 9,716.0 9,717.0 3.00 0.360 EXP/ MESAVERDE/ 9,772.0 9,773.0 3.00 0.360 EXP/ MESAVERDE/ 9,845.0 9,846.0 3.00 0.360 EXP/	60 EXP/	120.00	23.00 PRODUCTIO	.: 4
MESAVERDE/ 9,772.0 9,773.0 3.00 0.360 EXP/ MESAVERDE/ 9,845.0 9,846.0 3.00 0.360 EXP/		120.00	23.00 PRODUCTIO N	304
MESAVERDE/ 9,845.0 9,846.0 3.00 0.360 EXP/		120.00	23.00 PRODUCTIO N	1 75:
		120.00	23.00 PRODUCTIO N	255
5/6/2013 MESAVERDE/ 9,882.0 9,884.0 3.00 0.360 EXP/ 3.375		120.00	23.00 PRODUCTIO N	100

Plots

Wellbore Schematic 3.1



May 29, 2013 at 12:02 pm

					S ROCI			
				Opera	tion S	umma	ary Report	
Well: NBU 921-2	22K4CS (BLUE)						Spud Date: 12/	/28/2012
Project: UTAH-U	JINTAH		Site: NBL	J 921-22K	PAD			Rig Name No: SWABBCO 6/6
Event: COMPLE	ETION		Start Date	e: 4/30/20	13			End Date: 5/16/2013
Active Datum: F	RKB @4,911.00usft (a	above Mean Se	ea	UWI: NE	E/SW/0/9/	S/21/E/2	2/0/0/26/PM/S/17	'53/W/0/1640/0/0
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
4/4/2013	8:00 - 9:00	1.00	SUBSPR	35	A	Р		MIRU DELSCO SLICK LINE. RIH W/ 1-1/2" SINKER BARS. TAG FILL @ 9964'. F/C @ 10,005'. POOH RDMO DELSCO.
4/9/2013	-							
4/30/2013	12:30 - 13:45	1.25	SUBSPR	33	С	Р		FILL SURFACE CSG. MIRU CAMERON QUICK TEST. PRESSURE TEST CSG & FRAC VALVES 1ST PSI TEST T/ 7000 PSI. HELD FOR 15 MIN LOST 53 PSI. NO COMMUNICATION OR MIGRATION WITH SURFACE CSG BLEED OFF PSI.
								PRESSURE TEST 8 5/8 X 4 1/2 TO 505 PSI HELD FOR 5 MIN LOST -45 PSI,BLED PSI OFF, REINSTALLED POP OFF SWIFN SURFACE CSG HAD "0" PSI ON WELL
5/3/2013	7:00 - 10:00	3.00	SUBSPR	37		Р		PERF STG 1)PU 3 1/8 EXP GUN, 23 GM, .36 HOLE
0,0,20.10	.0.00	0.00	3333.11	o.		·		SIZE. 90 DEG PHASING. RIH PERF AS PER PERF DESIGN. POOH. SWIFW
5/6/2013	6:45 - 7:00	0.25	FRAC	48		Р		HSM, SPILL CONTAINMENT
	7:00 - 17:30	10.50	FRAC	36	В	Р		REFER TO STIMULATION PJR FOR FLUID, SAND AND CHEMICAL VOLUMES, ALL STAGES WERE PERFORATED ACCORDING TO PERF RECORD IN OPEN WELLS, ALL STAGES WERE STIMULATED TO VENDOR POST JOB REPORT. ALL PLUGS ARE HALIBURTON 8K CBPS FRAC STG #1] WHP=1,805#, BRK DN
								PERFS=4,469#, @=4.8 BPM, INTIAL ISIP=3,009#, FG=.75, FINAL ISIP=3,039#, FG=.75, SET PLUG & PERFORATE STG #2
								FRAC STG #2] WHP=2,855#, BRK DN PERFS=3,460#, @=4.9 BPM, INTIAL ISIP=2,961#, FG=.75, FINAL ISIP=3,316#, FG=.79,
								SET PLUG & PERFORATE STG #3 SWIFN.
5/7/2013	6:30 - 6:45	0.25	FRAC	48		Р		HSM, WORKING AROUND WIRELINE

5/29/2013 12:03:41PM 1

API Well Number: 43047525510000 US ROCKIES REGION **Operation Summary Report** Spud Date: 12/28/2012 Well: NBU 921-22K4CS (BLUE) Project: UTAH-UINTAH Site: NBU 921-22K PAD Rig Name No: SWABBCO 6/6 Event: COMPLETION End Date: 5/16/2013 Start Date: 4/30/2013 UWI: NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0 Active Datum: RKB @4,911.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 6:45 - 13:00 6.25 **FRAC** 36 В Ρ FRAC STG #3] WHP=2,145#, BRK DN PERFS=3,739#, @=4.8 BPM, INTIAL ISIP=2,632#, FG=.72, FINAL ISIP=3,020#, FG=.76, SET PLUG & PERFORATE STG #4 FRAC STG #4] WHP=1,970#, BRK DN PERFS=4,214#, @=4.8 BPM, INTIAL ISIP=2,442#, FG=.71, FINAL ISIP=2,961#, FG=.77, MISSFIRE, POOH FIX PROBLEM SET PLUG PERFORATE STG #5 SWIFN. 5/8/2013 6:45 - 7:00 0.25 **FRAC** STAYING AWAY FROM HIGH PRESSURE LINES 7:00 - 17:30 10.50 FRAC 36 В FRAC STG #5] WHP=1,842#, BRK DN PERFS=3,748#, @=4.7 BPM, INTIAL ISIP=2,568#, FG=.73, FINAL ISIP=3,064#, FG=.79, SET PLUG AND PERFORATE STG #6 FRAC STG #6] WHP=2,440#, BRK DN PERFS=4.6#, @=4.6 BPM, INTIAL ISIP=2,691#, FG=.75, FINAL ISIP=3,132#, FG=.80, SET PLUG AND PERFORATE STG #7 FRAC STG #7] WHP=953#, BRK DN PERFS=2,638#, @=4.8 BPM, INTIAL ISIP=1,928#, FG=.67, FINAL ISIP=2,579#, FG=.75, SET PLUUG AND PERFORATE STG #8 SWIFN. 6:45 - 7:00 5/9/2013 0.25 **FRAC** 48 Ρ HSM, PROPER PPE

5/29/2013 12:03:41PM 2

API Well Number: 43047525510000 US ROCKIES REGION **Operation Summary Report** Spud Date: 12/28/2012 Well: NBU 921-22K4CS (BLUE) Project: UTAH-UINTAH Site: NBU 921-22K PAD Rig Name No: SWABBCO 6/6 **Event: COMPLETION** End Date: 5/16/2013 Start Date: 4/30/2013 UWI: NE/SW/0/9/S/21/E/22/0/0/26/PM/S/1753/W/0/1640/0/0 Active Datum: RKB @4,911.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 7:00 - 18:00 11.00 **FRAC** 36 В Ρ FRAC STG #8] WHP=1,125#, BRK DN PERFS=2,759#, @=4.7 BPM, INTIAL ISIP=1,727#, FG=.65, FINAL ISIP=2,645#, FG=.77, SET PLUG AND PERFORATE STG #9 FRAC STG #9] WHP=912#, BRK DN PERFS=2,453#, @=4.9 BPM, INTIAL ISIP=1,924#, FG=.69, FINAL ISIP=3,026#, FG=.83, SET PLUG AND PERFORATE STG #10 FRAC STG #10] WHP=1.155#, BRK DN PERFS=2,860#, @=6.6 BPM, INTIAL ISIP=2,265#, FG=.74, FINAL ISIP=2,546#, FG=.78, SET PLUG AND PERFORATE STG #11 FRAC STG #11] WHP=2,020#, BRK DN PERFS=2,4676#, @=4.5 BPM, INTIAL ISIP=2,100#, FG=.73, FINAL ISIP=2,188#, FG=.74, SETPLUG AND PERFORATE STG #12 **SWIFN** 7:00 5/10/2013 - 15:00 8.00 **FRAC** 36 В Р FRAC STG 12)WHP 862 PSI, BRK 2470 PSI @ 4.7 BPM. ISIP 1525 PSI, FG. 0.66 ISIP 1974 PSI, FG. 0.72, NPI 449 PSI. SWI, XO T/ WL. PU 4 1/2 8K HAL CBP. RIH SET KILL PLUG @ 6750'. POOH. SWI. FINISH FRACING. TOTAL SAND = 331,174 LBS TOTAL CLFL = 14,219 BBL BOP'S 5/15/2013 7:00 - 7:30 0.50 **DRLOUT** 7:30 - 17:30 10.00 31 Р DRLOUT MIRU, NDWH, NU BOP'S, PU BIT, POBS, SN, TIH WITH 150 JTS J-55 TBG, PU 6' L-80 PUP JT, 62 JTS L-80 TBG, TAG KILL PLUG, PU PWR SWIVEL, BREAK CIRC, PRESSURE TEST BOP'S TO 3000#, MILL 6 PLUGS, 262 JTS, 8286.54', EOT SWIFN 5/16/2013 7:00 - 7:30 0.50 DRLOUT Р LANDING TBG

5/29/2013 12:03:41PM 3

				Opera	tion S	umma	ry Report	
Well: NBU 921-	22K4CS (BLUE)						Spud Date: 12	/28/2012
Project: UTAH-l	· · · · · · · · · · · · · · · · · · ·		Site: NBL	J 921-22k	(PAD			Rig Name No: SWABBCO 6/6
Event: COMPLE	FTION		Start Date	a: 4/30/20	112			End Date: 5/16/2013
	RKB @4,911.00usft (abo	ve Mean S		1		L /S/21/E/22	/0/0/26/PM/S/17	753/W/0/1640/0/0
Level)	11.D @ 1,011.000011 (abo	vo moan o	ou					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:30 - 17:00	9.50	DRLOUT	44	C	P		MILL 6 CBP'S, 305 JTS, 9630',C/O 40' SAND,TO PBTD 10,005', 316 JTS, POOH TO 9423.74', 297 JTS, LAND TBG, ND BOP'S, NUWH, POBS, 3000#, PRESSURE TEST FLOW LINE 3000#, RDMO TURNED TO PROD 3:00 PM PLUG# 1 6750' 10' SAND 5 MIN 0# KICK PLUG# 2 7090' 30' SAND 5 MIN 0# KICK PLUG# 3 7326' 25' SAND 5 MIN 100# KICK PLUG# 4 7540' 25' SAND 5 MIN 100# KICK PLUG# 5 7800' 30' SAND 5 MIN 150# KICK PLUG# 6 8196' 30' SAND 5 MIN 100# KICK PLUG# 7 8470' 40' SAND 5 MIN 100# KICK PLUG# 8 8695' 30' SAND 5 MIN 100# KICK PLUG# 9 8896' 30' SAND 5 MIN 100# KICK PLUG# 10 9099' 30' SAND 5 MIN 100# KICK PLUG# 11 9435' 25' SAND 5 MIN 100# KICK PLUG# 12 9630' 30' SAND
	17:00 - 17:00	0.00	DRLOUT	50				LTR 11,419 BBLS WELL TURNED TO SALES @ 1240 HR ON 5/16/2013. 780 MCFD, 1920 BWPD, FCP 2033#, FTP 1746#, 20/64" CK.

5/29/2013 12:03:41PM 4

API Well Number: 4304752 Site: NBU 921-22K PAD

Scientific Drilling

Well: NBU 921-22K4CS

Wellbore: OH

Design: OH









Azimuths to True North Magnetic North: 10.889

> Magnetic Field Strength: 52170.9snT Dip Angle: 65.83° Date: 02/05/2013







PROJECT DETAILS: UTAH - UTM (feet), NAD27, Zone 12N

Geodetic System: Universal Transverse Mercator (US Survey Feet)
Datum: NAD 1927 (NADCON CONUS)

Ellipsoid: Clarke 1866 Zone: Zone 12N (114 W to 108 W) Location: SECTION 22 T9S R21E System Datum: Mean Sea Level

Design: OH (NBU 921-22K4CS/OH)

RECEIVoreated By: Gable Mendall 1 Oate: 9:22 March 31 2013



US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N NBU 921-22K PAD NBU 921-22K4CS

OH

Design: OH

Standard Survey Report

01 March, 2013



API Well Number: 43047525510000



SDI Survey Report



US ROCKIES REGION PLANNING Company:

Project: UTAH - UTM (feet), NAD27, Zone 12N

NBU 921-22K PAD Site: Well: NBU 921-22K4CS

Wellbore: ОН Design: ОН

Geo Datum:

Local Co-ordinate Reference:

Well NBU 921-22K4CS

GL 4887 & KB 24 @ 4911.00ft (H&P 318) GL 4887 & KB 24 @ 4911.00ft (H&P 318)

North Reference:

Minimum Curvature

Survey Calculation Method:

Database:

TVD Reference:

MD Reference:

EDM 5000.1 Single User Db

UTAH - UTM (feet), NAD27, Zone 12N Project

Map System: Universal Transverse Mercator (US Survey Feet) NAD 1927 (NADCON CONUS)

System Datum:

Mean Sea Level

Map Zone: Zone 12N (114 W to 108 W)

Site NBU 921-22K PAD, SECTION 22 T9S R21E

Northing: 14,536,368.06 usft Site Position: Latitude: 40.0191630 From: Lat/Long Easting: 2,048,967.31 usft Longitude: -109.5408140 **Position Uncertainty:** 13.200 in 0.94°

0.00 ft Slot Radius: **Grid Convergence:**

Well NBU 921-22K4CS, 1753 FSL 1640 FWL **Well Position** +N/-S 0.00 ft Northing: 14,536,370.04 usft Latitude: 40.0191680 +E/-W 0.00 ft Easting: 2,048,977.08 usft Longitude: -109.5407790 0.00 ft 4,887.00 ft **Position Uncertainty** Wellhead Elevation: ft **Ground Level:**

Wellbore	ОН				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	02/05/13	10.88	65.83	52,171

ОН Design Audit Notes: ACTUAL Version: 1.0 Phase: Tie On Depth: 0.00 **Vertical Section:** Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 110.23

Survey Program	Date 03/01/13		
From (ft)	To (ft) Survey (Wellbore)	Tool Name	Description
20.00 2,961.00	2,850.00 Survey #1 SDI MWD SURFACE (OH) 10,065.00 Survey #2 SDI MWD PRODUCTION (OH)	SDI MWD SDI MWD	SDI MWD - Standard ver 1.0.1 SDI MWD - Standard ver 1.0.1

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
20.00	0.00	0.00	20.00	0.00	0.00	0.00	0.00	0.00	0.00
173.00	0.62	302.97	173.00	0.45	-0.69	-0.81	0.41	0.41	0.00
FIRST SDI N	MWD SURFACE	SURVEY							
257.00	0.44	312.37	256.99	0.92	-1.31	-1.55	0.24	-0.21	11.19
344.00	1.01	117.81	343.99	0.78	-0.88	-1.10	1.66	0.66	190.16
434.00	2.81	116.11	433.94	-0.56	1.80	1.88	2.00	2.00	-1.89
524.00	4.31	116.09	523.76	-3.02	6.82	7.44	1.67	1.67	-0.02
614.00	5.98	112.77	613.39	-6.32	14.18	15.49	1.88	1.86	-3.69
704.00	7.83	108.91	702.74	-10.12	24.30	26.30	2.12	2.06	-4.29



SDI Survey Report

TVD Reference:

MD Reference:

North Reference:



Company: US ROCKIES REGION PLANNING

Project: UTAH - UTM (feet), NAD27, Zone 12N

Site: NBU 921-22K PAD Well: NBU 921-22K4CS

Wellbore: OH
Design: OH

Local Co-ordinate Reference:

Well NBU 921-22K4CS

GL 4887 & KB 24 @ 4911.00ft (H&P 318) GL 4887 & KB 24 @ 4911.00ft (H&P 318)

True

Survey Calculation Method: Minimum Curvature

Database: EDM 5000.1 Single User Db

Measured Depth			Vertical			Vertical	Dogleg	Build	Turn
(ft)	Inclination (°)	Azimuth (°)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Section (ft)	Rate (°/100ft)	Rate (°/100ft)	Rate (°/100ft)
794.00	8.97	106.88	791.77	-14.14	36.82	39.44	1.31	1.27	-2.26
884.00	10.51	107.61	880.47	-18.67	51.36	54.64	1.72	1.71	0.81
974.00	11.34	106.97	968.84	-23.73	67.64	71.68	0.93	0.92	-0.71
1,064.00	11.61	106.45	1,057.04	-28.88	84.79	89.55	0.32	0.30	-0.58
1,154.00	11.87	107.59	1,145.16	-34.24	102.30	107.83	0.39	0.29	1.27
1,244.00	12.31	107.59	1,233.16	-39.94	120.27	126.66	0.49	0.49	0.00
1,334.00	11.34	106.09	1,321.25	-45.29	137.92	145.07	1.13	-1.08	-1.67
1,424.00	10.82	105.13	1,409.57	-49.95	154.57	162.31	0.61	-0.58	-1.07
1,514.00	10.55	106.97	1,498.01	-54.56	170.61	178.95	0.48	-0.30	2.04
1,604.00	10.90	108.20	1,586.44	-59.62	186.57	195.68	0.46	0.39	1.37
1,694.00	10.90	109.61	1,674.82	-65.13	202.67	212.69	0.30	0.00	1.57
1,784.00	11.34	108.55	1,763.13	-70.80	219.08	230.04	0.54	0.49	-1.18
1,874.00	11.17	108.29	1,851.40	-76.35	235.74	247.60	0.20	-0.19	-0.29
1,964.00	10.99	109.17	1,939.72	-81.91	252.12	264.89	0.27	-0.20	0.98
2,054.00	11.07	108.62	2,028.06	-87.48	268.41	282.11	0.15	0.09	-0.61
2,144.00	11.19	107.97	2,116.36	-92.94	284.91	299.47	0.19	0.13	-0.72
2,234.00	10.55	106.81	2,204.75	-98.01	301.10	316.42	0.75	-0.71	-1.29
2,324.00	10.11	106.97	2,293.29	-102.70	316.54	332.53	0.49	-0.49	0.18
2,414.00	9.50	106.88	2,381.97	-107.16	331.21	347.83	0.68	-0.68	-0.10
2,504.00	9.50	107.32	2,470.74	-111.53	345.40	362.66	0.08	0.00	0.49
2,594.00	9.58	106.71	2,559.50	-115.89	359.67	377.56	0.14	0.09	-0.68
2,684.00	9.58	107.24	2,648.24	-120.27	373.99	392.51	0.10	0.00	0.59
2,774.00	10.29	107.06	2,736.89	-124.85	388.83	408.02	0.79	0.79	-0.20
2,850.00	11.34	107.41	2,811.54	-129.07	402.45	422.26	1.38	1.38	0.46
	WD SURFACE S 11.21	102.74	2,920.40	-134.72	423.39	443.85	0.83	-0.12	-4.21
2,961.00	IWD PRODUCTI		2,920.40	-134.72	423.39	443.00	0.63	-0.12	-4.21
3,055.00	11.28	104.05	3,012.59	-138.96	441.22	462.05	0.28	0.07	1.39
3,150.00	9.26	103.72	3,106.07	-143.03	457.66	478.89	2.13	-2.13	-0.35
3,244.00	7.43	106.21	3,199.07	-146.52	470.84	492.46	1.98	-1.95	2.65
3,339.00	5.51	108.22	3,293.46	-149.67	481.07	503.15	2.03	-2.02	2.12
3,433.00	3.78	103.70	3,387.15	-151.81	488.37	510.74	1.88	-1.84	-4.81
3,527.00	1.08	117.54	3,481.05	-152.95	492.17	514.70	2.92	-2.87	14.72
3,622.00	0.20	182.24	3,576.05	-153.53	492.96	515.64	1.06	-0.93	68.11
3,716.00	0.31	205.67	3,670.05	-153.93	492.84	515.66	0.16	0.12	24.93
3,811.00	0.55	200.51	3,765.04	-154.59	492.57	515.64	0.26	0.25	-5.43
3,905.00	1.06	196.07	3,859.04	-155.84	492.17	515.70	0.55	0.54	-4.72
4,000.00	1.34	196.03	3,954.01	-157.76	491.62	515.84	0.29	0.29	-0.04
4,094.00	1.25	177.18	4,047.99	-159.84	491.37	516.32	0.46	-0.10	-20.05
4,189.00	1.40	171.00	4,142.97	-162.02	491.60	517.30	0.22	0.16	-6.51
4,283.00	0.38	177.12	4,236.95	-163.46	491.79	517.98	1.09	-1.09	6.51
4,377.00	0.76	213.84	4,330.95	-164.29	491.46	517.96	0.54	0.40	39.06



SDI Survey Report



Company: US ROCKIES REGION PLANNING

Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-22K PAD

 Well:
 NBU 921-22K4CS

Wellbore: OH
Design: OH

Local Co-ordinate Reference:

TVD Reference: GL 4887 & KB 24 @ 4911.00ft (H&P 318)

MD Reference: GL 4887 & KB 24 @ 4911.00ft (H&P 318)

North Reference:

Survey Calculation Method: Minimum Curvature

Database: EDM 5000.1 Single User Db

Well NBU 921-22K4CS

: On				Database:			DIVI 5000. I SIII		
y Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,566.00	0.61	178.43	4,519.93	-166.91	490.37	517.83	0.63	-0.49	-28.82
4,661.00	0.68	173.66	4,614.92	-167.97	490.44	517.03	0.09	0.07	-5.02
4,755.00	0.88	169.26	4,708.91	-169.24	490.64	518.89	0.09	0.07	-4.68
4,850.00	0.62	97.55	4,803.90	-170.02	490.04	510.09	0.22	-0.27	-75.48
4,944.00	0.02	128.57	4,803.90	-170.02	491.26	520.83	0.93	0.12	33.00
4,944.00	0.73	120.37	4,097.90	-170.40	492.20	320.63	0.40	0.12	33.00
5,038.00	0.86	145.73	4,991.89	-171.42	493.12	521.98	0.29	0.14	18.26
5,132.00	0.95	42.62	5,085.88	-171.43	494.05	522.85	1.51	0.10	-109.69
5,226.00	0.81	56.21	5,179.87	-170.48	495.13	523.53	0.27	-0.15	14.46
5,321.00	0.62	97.37	5,274.86	-170.18	496.19	524.43	0.56	-0.20	43.33
5,415.00	0.92	115.17	5,368.86	-170.56	497.38	525.68	0.40	0.32	18.94
5,510.00	0.62	352.61	5,463.85	-170.38	498.01	526.20	1.43	-0.32	-129.01
5,604.00	0.44	333.27	5,557.85	-169.55	497.78	525.70	0.27	-0.19	-20.57
5,698.00	0.00	103.78	5,651.85	-169.23	497.62	525.44	0.47	-0.47	0.00
5,793.00	1.37	10.11	5,746.84	-168.11	497.81	525.24	1.44	1.44	0.00
5,887.00	1.10	9.52	5,840.82	-166.11	498.16	524.87	0.29	-0.29	-0.63
5,982.00	0.64	31.25	5,935.81	-164.76	498.59	524.80	0.59	-0.48	22.87
6,076.00	0.04	43.34	6,029.80	-163.84	499.30	525.16	0.39	0.16	12.86
		62.12	6,124.79			525.66			
6,171.00 6,265.00	0.44	106.72	6,124.79	-163.19	500.08 500.54	526.05	0.42	-0.37 -0.28	19.77 47.45
	0.18			-163.07			0.36		
6,359.00	0.38	101.23	6,312.79	-163.17	500.98	526.50	0.21	0.21	-5.84
6,454.00	0.53	151.07	6,407.79	-163.62	501.51	527.15	0.43	0.16	52.46
6,548.00	0.62	170.76	6,501.78	-164.50	501.80	527.72	0.23	0.10	20.95
6,642.00	0.18	290.20	6,595.78	-164.95	501.74	527.83	0.77	-0.47	127.06
6,737.00	0.50	221.77	6,690.78	-165.21	501.32	527.53	0.49	0.34	-72.03
6,831.00	0.70	183.41	6,784.77	-166.09	501.02	527.54	0.47	0.21	-40.81
6,926.00	0.79	179.99	6,879.77	-167.32	500.98	527.94	0.11	0.09	-3.60
7,020.00	0.99	182.94	6,973.75	-168.78	500.94	528.40	0.22	0.21	3.14
7,115.00	1.02	257.47	7,068.74	-169.78	500.07	527.93	1.28	0.03	78.45
7,209.00	1.02	241.20	7,162.73	-170.37	498.52	526.68	0.31	0.00	-17.31
7,303.00	0.90	269.30	7,256.72	-170.78	497.05	525.44	0.51	-0.13	29.89
7,398.00	1.08	325.79	7,351.70	-170.05	495.80	524.02	1.00	0.19	59.46
7,492.00	0.90	317.00	7,331.70	-170.05	493.80	522.64	0.25	-0.19	-9.35
7,492.00	0.90	309.41	7,445.69	-166.76 -167.86	494.80	522.64 521.41	0.25	-0.19 -0.18	-9.35 -8.07
7,580.00	0.73	312.56	7,633.67	-166.93	493.63	521.41 520.10	0.21	-0.16 0.27	3.35
7,774.00	0.79	302.05	7,727.66	-166.05	491.64	518.73	0.27	-0.20	-11.18
7,868.00	0.62	248.01	7,821.65	-165.89	490.62	517.72	0.70	-0.18	-57.49
7,962.00	0.21	80.51	7,915.65	-166.05	490.32	517.49	0.88	-0.44	-178.19
8,057.00	0.10	41.26	8,010.65	-165.96	490.54	517.67	0.15	-0.12	-41.32
8,151.00	0.26	355.68	8,104.65	-165.69	490.58	517.61	0.22	0.17	-48.49
8,245.00	0.34	151.39	8,198.65	-165.72	490.70	517.73	0.62	0.09	165.65
8,339.00	0.68	150.41	8,292.65	-166.45	491.11	518.37	0.36	0.36	-1.04
8,433.00	0.26	330.63	8,386.64	-166.75	491.28	518.63	1.00	-0.45	-191.26
8,527.00	0.20	46.40	8,480.64	-166.45	491.29	518.54	0.30	-0.45	80.61
8,622.00	0.60	132.55	8,575.64	-166.67	491.78	519.08	0.65	0.42	90.68

API Well Number: 43047525510000



SDI Survey Report



Company: US ROCKIES REGION PLANNING

Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-22K PAD

 Well:
 NBU 921-22K4CS

Wellbore: OH
Design: OH

Local Co-ordinate Reference:

TVD Reference:
MD Reference:

North Reference:

Survey Calculation Method:

Database:

Well NBU 921-22K4CS

GL 4887 & KB 24 @ 4911.00ft (H&P 318) GL 4887 & KB 24 @ 4911.00ft (H&P 318)

True

Minimum Curvature

EDM 5000.1 Single User Db

Manaurad			Vartical			Vartical	Dawlan	Duild	T
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
8,716.00	0.57	131.90	8,669.64	-167.32	492.49	519.97	0.03	-0.03	-0.69
8,811.00	0.61	147.18	8,764.63	-168.06	493.12	520.81	0.17	0.04	16.08
8,905.00	0.87	155.16	8,858.62	-169.13	493.69	521.71	0.30	0.28	8.49
8,999.00	1.07	167.72	8,952.61	-170.63	494.17	522.69	0.31	0.21	13.36
9,094.00	1.40	145.29	9,047.59	-172.45	495.02	524.12	0.61	0.35	-23.61
9,188.00	0.42	131.42	9,141.58	-173.62	495.93	525.38	1.06	-1.04	-14.76
9,283.00	0.42	90.84	9,236.57	-173.86	496.54	526.03	0.31	0.00	-42.72
9,377.00	0.09	136.22	9,330.57	-173.92	496.94	526.42	0.39	-0.35	48.28
9,471.00	0.69	152.95	9,424.57	-174.48	497.25	526.91	0.64	0.64	17.80
9,566.00	0.82	184.00	9,519.56	-175.66	497.46	527.52	0.45	0.14	32.68
9,660.00	1.23	161.97	9,613.55	-177.29	497.73	528.33	0.60	0.44	-23.44
9,755.00	1.23	150.18	9,708.53	-179.15	498.55	529.74	0.27	0.00	-12.41
9,849.00	1.26	160.25	9,802.50	-181.00	499.40	531.18	0.23	0.03	10.71
9,943.00	1.38	147.83	9,896.48	-182.93	500.35	532.74	0.33	0.13	-13.21
10,015.00	1.32	135.86	9,968.46	-184.26	501.39	534.17	0.40	-0.08	-16.63
LAST SDI M	ND PRODUCTIO	N SURVEY							
10,065.00	1.32	135.86	10,018.45	-185.08	502.19	535.21	0.00	0.00	0.00

Design Annotations					
Measur			Local Coordinates	5	
Depth (ft)	ı Dej (f			E/-W (ft)	Comment
17	3.00	173.00	0.45	-0.69	FIRST SDI MWD SURFACE SURVEY
2,85	0.00 2	2,811.54	-129.07	402.45	LAST SDI MWD SURFACE SURVEY
2,96	1.00 2	2,920.40	-134.72	423.39	FIRST SDI MWD PRODUCTION SURVEY
10,01	5.00 9	,968.46	-184.26	501.39	LAST SDI MWD PRODUCTION SURVEY
10,06	5.00 10),018.45	-185.08	502.19	SDI PROJECTION TO BIT

Checked By:	Approved By:	Date: